

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				80% FED 20% STAT ROADWAY	80% FED 20% STATE BRIDGE	80% FED 20% STATE BRIDGE	80% FED 20% STATE BRIDGE	80% FED 20% STATE BRIDGE	100% CITY BRIDGE	
				0004 S.N.	0011 101-0195	0011 101-0196	0011 101-0197	0011 101-0198	0011 CITY OF ROCKFORD	
				<i>URBAN</i>						
28000305	TEMPORARY DITCH CHECKS	FOOT	1,005	1,005						
28000400	PERIMETER EROSION BARRIER	FOOT	3,247	3,247						
28000500	INLET AND PIPE PROTECTION	EACH	9	9						
28001000	AGGREGATE (EROSION CONTROL)	TON	114	114						
28100105	STONE RIPRAP, CLASS A3	SO YD	70	70						
28100109	STONE RIPRAP, CLASS A5	SO YD	3124		820	820	742	742		
28200200	FILTER FABRIC	SO YD	3194	70	820	820	742	742		
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	11,348	11,348						
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SO YD	2,470	2,470						
31200100	STABILIZED SUBBASE 4"	SO YD	1,158	1,158						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	12	12						
40600837	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70	TON	2,433	2,433						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1,833	1,833						
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,006	1,006						

△ DENOTES SPECIALTY ITEM
 ** 100% STATE

FILE NAME : D:\2013\11-15-13\11-15-13-1300.dgn
 MODEL : Default
 PLOT DRIVER : vbi...DOT.PDF...11-15-13-1300.dgn

 QUIGG ENGINEERING INC	USER NAME : rgoertz DESIGNED - CMS DRAWN - TKW CHECKED - CMS DATE - 07/01/2013	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. : 301 SECTION : 3BR & 3BR-1 COUNTY : WINNEBAGO TOTAL SHEETS : 290 SHEET NO. : 7 CONTRACT NO. : 64019
	PLOT SCALE : 48.8888' / in. PLOT DATE : 9/3/2013	SCALE: SHEET NO. OF SHEETS STA. TO STA.			FED. ROAD DIST. NO. : ILLINOIS FED. AID PROJECT