

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				80% FED 20% STAT ROADWAY 0004 S.N.	80% FED 20% STATE BRIDGE 0011 101-0195	80% FED 20% STATE BRIDGE 0011 101-0196	80% FED 20% STATE BRIDGE 0011 101-0197	80% FED 20% STATE BRIDGE 0011 101-0198	100% CITY BRIDGE 0011 CITY OF ROCKFORD
				URBAN					
51204100	TEST PILE STEEL HP14X117	EACH	2		1	1			
51204650	PILE SHOES	EACH	512		134	134	122	122	
51500100	NAME PLATES	EACH	4		1	1	1	1	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	373		98.5	98.5	88	88	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	48		12	12	12	12	
52100520	ANCHOR BOLTS, 1"	EACH	96		24	24	24	24	
52100540	ANCHOR BOLTS, 1 1/2"	EACH	48		12	12	12	12	
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	49	49					
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	366	366					
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	4	4					
54245405	INLET BOX, STANDARD 542506	EACH	1	1					
54261324	CONCRETE END SECTION, STANDARD 542001, 24", 1:3	EACH	4	4					
54261424	CONCRETE END SECTION, STANDARD 542001, 24", 1:4	EACH	1	1					
58700300	CONCRETE SEALER	SO FT	8,139		2,024	1,998	2,058	2,059	

△ DENOTES SPECIALTY ITEM

•• 100% STATE

FILE NAME : 0264019-311-500.dgn  
 MODEL :  
 PLOT DRIVER : V8...IDOT.PDF...11x17.ctb



USER NAME : rgoertz	DESIGNED - CMS	REVISED -
PLOT SCALE : 40.0000' / 1"	DRAWN - TKW	REVISED -
PLOT DATE : 9/3/2013	CHECKED - CMS	REVISED -
	DATE - 07/01/2013	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 301	SECTION 3BR & 3BR-1	COUNTY WINNEBAGO	TOTAL SHEETS 290	SHEET NO. 11
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
CONTRACT NO. 64D19				