

LOCATION			21101615	25200110	25200200	28000250			
			AREA MEASURED IN CADD	TOPSOIL FURNISH AND PLACE, 4"	SODDING, SALT TOLERANT	SUPPLEMENTAL WATERING	TEMPORARY EROSION CONTROL SEEDING		
STATION	STATION	LT/RT	(SQ FT)	(SQ YD)	(SQ YD)	(UNIT)	RATE (LBS/ACRE)	APPLICATIONS	(POUND)
IL 84									
318+00.00	318+13.00	LT	173	20	20		100	3	2
318+48.00	318+89.00	LT	133	15	15		100	3	1
318+58.00	319+30.00	RT	816	91	91		100	3	6
320+63.00	321+04.00	LT	1267	141	141		100	3	9
320+91.00	321+71.00	RT	1196	133	133		100	3	9
321+90.00	323+05.00	LT	450	50	50		100	3	4
322+52.00	323+05.00	RT	279	31	31		100	3	2
FULTON ROAD									
8+55.00	9+11.00	LT	221	25	25		100	3	2
FULTON STREET									
10+30.00	11+00.00	LT	706	79	79		100	3	5
TOTAL				585	585	6			40

LOCATION			LENGTH	AREA	SUBGRADE WIDTH	AGGREGATE SUBGRADE IMPROVEMENT 24"
STATION	STATION	OFFSET	(FT)	(SQ FT)	(FT)	(SQ YD)
IL 84						
317+40.00	318+33.98	LT	93.98		19.78	207
317+45.00	318+30.98	RT	85.98		20.24	194
FULTON ROAD						
9+05.00	9+36.50		31.5		27.08	95
9+36.50	9+87.79		51.29		24	137
NORTHWEST QUADRANT		LT		513		57
SOUTHWEST QUADRANT		RT		314		35
LT SIDE ON FULTON STREET		LT		555		62
FULTON STREET						
10+12.77	10+31.90		19.13		20	43
10+31.90	10+50.00		18.1		26.16	53
10+50.00	11+00.00		50		24.16	135
NORTHEAST QUADRANT				223		25
SOUTHEAST QUADRANT				93		11
TOTAL						1,054

LOCATION	OFFSET	AREA	40200100			PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH
			AGGREGATE SURFACE COURSE, TYPE A			
			THICKNESS	APPLICATION RATE		
LT/RT	(SQ FT)	(INCH)	(TON/CY)	(TON)	(SQ YD)	
STA. 317+40 TO STA. 318+00	LT	613	8.00	2.05	32	
STA. 317+70	LT	675				75
STA. 317+75	RT	675				75
STA. 317+45 TO STA. 318+58	RT	1656	8.00	2.05	84	
TOTAL					116	150

LOCATION		LENGTH	WIDTH	40600982	44000155
STATION	STATION	(FOOT)	(FOOT)	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"
				(SQ YD)	(SQ YD)
321+51.08	322+75.00	123.92	24		331
322+75.00	323+05.00	30.00	24	80	
TOTAL				80	331

LOCATION		28000305
STATION	OFFSET	TEMPORARY DITCH CHECKS
		FOOT
FULTON STREET		
10+53.00	16' LT	10
10+95.00	13' LT	10
TOTAL		20

THE SCHEDULES DO NOT INCLUDE QUANTITIES FOR THE SANITARY LIFT STATION PLANS OR LIGHTING PLANS.



USER NAME = gjameson	DESIGNED -	REVISED
FILE NAME = 264E08-SHT-500.dgn	CHECKED -	REVISED
PLOT SCALE = 10.0000' / IN.	DRAWN -	REVISED
PLOT DATE = 8/5/2013	CHECKED -	REVISED

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES		
IL ROUTE 84 OVER APPLE RIVER		
SCALE: NTS	SHEET NO. 1 OF 9 SHEETS	STA. TO STA.

F.A.P. RTE. 308	SECTION 103BR-4	COUNTY JO DAVIESS	TOTAL SHEETS 159	SHEET NO. 17
CONTRACT NO. 64E08				
ILLINOIS FED. AID PROJECT				