

* Elevations taken from existing 1983 plans and have not been adjusted to the NAVD 88 Datum.
 ** Dimensions parallel to wingwall.

LEGEND

- Indicates Superstructure items to be removed
- Indicates Substructure items to be removed

REMOVAL ELEVATION

The Structural Removal Plan is for information only and does not relieve the Contractor from the responsibility of submitting a Demolition Plan in accordance with the Contract Special Provisions.

Notes:

The removal of the existing structure shall be in accordance with Article 501 of the Standard Specifications, unless noted otherwise. Removal of existing railing and wearing surface is included in the pay item Removal of Existing Structures. Removal and salvage of the existing Lighting Units is included in the pay item Removal of Lighting Unit, Salvage. See Special Provisions.

The Contractor is advised that the existing bearing pads at each abutment contain asbestos. All necessary precautions shall be taken in removing, handling, transporting and disposing of the bearing pads. See Special Provisions.

In addition to the Requirements for Structural Assessment for Contractors Means and Methods, all of the Contractors work shall comply with the requirements outlined in the Special Provision for Construction Vibration Monitoring.

The existing PPC deck beams shall not be demolished in place, but shall be removed by hoisting to prevent damage to the arch span below.


A temporary support system will be required for stage removal of the concrete arch segments. See Special Provisions.

Removal of the existing pier caps during Stage I Removal will require Temporary Shoring. See sheet 7 of 60 for details.

Work this sheet with sheets 5 and 7 of 60.

BILL OF MATERIAL

ITEM	UNIT	TOTAL
Removal of Existing Structures	Each	1
Asbestos Bearing Pad Removal	Each	68
Temporary Support System	L. Sum	1
Removal of Lighting Unit, Salvage	Each	8



USER NAME = dheberling	DESIGNED - SBC	REVISED
FILE NAME = 0430028-64E08.dgn	CHECKED - BRD	REVISED
PLOT SCALE = 0:2.00000 '1' / in.	DRAWN - DLH	REVISED
PLOT DATE = 9/26/2013	CHECKED - SBC	REVISED

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**STRUCTURE REMOVAL PLAN AND DETAILS
STRUCTURE NO. 043-0080**

SHEET NO. 6 OF 60 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
308	103BR-4	JoDAVISS	159	56
CONTRACT NO. 64E08				
ILLINOIS FED. AID PROJECT				