



* Tilt #9 b104 (E), b105 (E), b106 (E), and b110 (E) bars as required to maintain clearance.
 ** Preformed Flexible Foam Expansion Joint Filler according to Article 1051.09 of the Standard Specifications, full depth of slab and sidewalk, full length of wingwall, typ. each wingwall. Cost included with Concrete Superstructure.
 # Dimensions are radial to ϕ Roadway and P.G.

MIN. BAR LAP
 #5 bars = 2'-6"

Notes:
 See Sheet 22 of 60 for Detail A and Section C-C.
 See Sheet 24 of 60 for Sections D-D, E-E, F-F, G-G, and Bill of Material.
 Place longitudinal bars in approach slab parallel to a chord intersecting roadway centerline at Sta. 321+21.41 and Sta. 321+51.08.
 See roadway plans for additional sidewalk details not shown.
 The sidewalk is cast monolithically over the north abutment backwall.
 See Sheet 35 of 60 for details.