


BILL OF MATERIALS

ITEMS	UNITS	QUANTITY
TOPSOIL FURNISH AND PLACE, 4"	SO YD	905
SODDING, SALT TOLERANT	SO YD	905
PERIMETER EROSION BARRIER	FOOT	338
INLET FILTERS	EACH	6
HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/2"	SO YD	34
PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCHES	SO YD	13
PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCHES	SO FT	125
COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	20
PAVEMENT REMOVAL	SO YD	185
DRIVEWAY PAVEMENT REMOVAL	SO YD	13
COMBINATION CURB AND GUTTER REMOVAL	FOOT	20
SIDEWALK REMOVAL	SO FT	125
CONNECTION TO EXISTING SEWER	EACH	2
ABANDON AND FILL EXISTING SANITARY MANHOLE	EACH	1
SANITARY SEWER LIFT STATION	L SUM	1
DIRECTIONAL BORING	FOOT	256
ABANDON AND FILL EXISTING SANITARY SEWER	EACH	3
SANITARY FORCE MAIN, 4"	FOOT	256
MANHOLES, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3
SANITARY MANHOLES TO BE REMOVED	EACH	1
SANITARY SEWER 8"	FOOT	263
TEMPORARY PAVEMENT	SO YD	151



- INDEX OF SHEETS**
- 1 GENERAL SITE PLAN AND BILL OF MATERIALS
 - 2 MAINTENANCE OF TRAFFIC STAGE 1
 - 3 MAINTENANCE OF TRAFFIC STAGE 2
 - 4 MAINTENANCE OF TRAFFIC STAGE 3
 - 5 PLAN AND PROFILE, STA 10+00
 - 6 PLAN AND PROFILE, STA 50+00
 - 7 LIFT STATION DETAILS
 - 8 MISCELLANEOUS DETAILS
 - 9 EROSION CONTROL PLAN
 - 10 LIGHTING PLAN

ADDITIONAL WORK BY VILLAGE

ITEMS	UNITS	QUANTITY
PAVEMENT REMOVAL	SO YD	110
HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/2"	SO YD	11
CONNECTION TO EXISTING SEWER	EACH	1
GATE VALVE, 8" WITH VAULT BOX	EACH	4
EXISTING WATER MAIN REPAIR	EACH	1
SANITARY SEWER 8"	FOOT	192
TEMPORARY PAVEMENT	SO YD	99
UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	326
ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 2-1/C NO. 4	FOOT	919

FILE NAME: G:\Projects\2012\12-159A\CADD_Drawing\12-159A - Site Plan.dgn
 DATE: 8/6/2013



USER NAME = tizerst	DESIGNED -	REVISED -
PLOT SCALE = 40.0000' / in.	DRAWN - YG	REVISED -
PLOT DATE = 8/6/2013	CHECKED - TMH	REVISED -
	DATE - 09/14/12	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL ROUTE 84
OVER APPLE RIVER**

**GENERAL SITE PLAN AND
BILL OF MATERIALS**

F.A. RTE. 308	SECTION 103 BR-4	COUNTY JO DAVIESS	TOTAL SHEETS 159	SHEET NO. 139
CONTRACT NO.			ILLINOIS FED. AID PROJECT	

SCALE: 1"=20' SHEET NO. 1 OF 10 SHEETS STA. TO STA.