

SUMMARY OF QUANTITIES

BRIDGE
037-0048

DOUBLE
BOX

ACRS ACHSIP

80% FED 20% STATE 0040	80% FED 20% STATE 0011	90% FED 10% STATE 0021	80% FED. 20% STATE 0011
------------------------------	------------------------------	------------------------------	-------------------------------

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
50200300	COFFERDAM EXCAVATION	CU YD	54		54		
50201101	COFFERDAM (TYPE 1) (LOCATION - 1)	EACH	1		1		
50201102	COFFERDAM (TYPE 1) (LOCATION - 2)	EACH	1		1		
50300225	CONCRETE STRUCTURES	CU YD	169.7		169.7		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	325.6		325.6		
50300260	BRIDGE DECK GROOVING	SQ YD	596		596		
50300280	CONCRETE ENCASEMENT	CU YD	4.2		4.2		
50300300	PROTECTIVE COAT	SQ YD	725		725		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	97,290		97,290		
51201600	FURNISHING STEEL PILES HP12X53	FOOT	295		295		
51201610	FURNISHING STEEL PILES HP12X63	FOOT	609		609		
51202305	DRIVING PILES	FOOT	295		295		
51203600	TEST PILE STEEL HP12X53	EACH	2		2		
51500100	NAME PLATES	EACH	8	6	1		1
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 01	EACH	1	1			
54001002	BOX CULVERT END SECTIONS, CULVERT NO. 02	EACH	2	2			
54001003	BOX CULVERT END SECTIONS, CULVERT NO. 03	EACH	4				4
54001004	BOX CULVERT END SECTIONS, CULVERT NO. 04	EACH	4	4			
54001005	BOX CULVERT END SECTIONS, CULVERT NO. 05	EACH	2	2			
54010603	PRECAST CONCRETE BOX CULVERTS 6' X 3'	FOOT	76	76			
54010906	PRECAST CONCRETE BOX CULVERTS 9' X 6'	FOOT	160	160			
54011206	PRECAST CONCRETE BOX CULVERTS 12' X 6'	FOOT	136				136
54011208	PRECAST CONCRETE BOX CULVERTS 12' X 8'	FOOT	102	102			
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	101	101			

* SPECIALTY ITEMS
 Δ 100% STATE

Rev.