

SCHEDULE OF QUANTITIES

44004250	PAVED SHOULDER REMOVAL LOCATION	SQ YD	COMMENTS				
	STA 317+83.40 TO 318+66.60	55		50101200	REMOVAL OF EXISTING STRUCTURES NO. 10 LOCATION	EACH	COMMENTS
	STA 324+39.70 TO 324+78.80	26			STA 467+10	1	SEE SPECIAL PROVISIONS FOR DETAILS
	STA 338+93.30 TO 339+36.60	29				TOTAL	1
	STA 372+49.88 TO 374+88.25	159					
	STA 375+75.32 TO 378+00.00	150					
	STA 378+89.40 TO 379+24.40	23		50101300	REMOVAL OF EXISTING STRUCTURES NO. 11 LOCATION	EACH	COMMENTS
	STA 383+65.00 TO 384+06.60	28			STA 479+36	1	SEE SPECIAL PROVISIONS FOR DETAILS
	STA 393+36.66 TO 393+92.35	37				TOTAL	1
	STA 396+81.60 TO 397+53.50	48					
	STA 462+02.20 TO 462+70.85	46					
	STA 466+09.80 TO 467+50.20	94		50101400	REMOVAL OF EXISTING STRUCTURES NO. 12 LOCATION	EACH	COMMENTS
	STA 479+08.80 TO 479+63.60	37			STA 492+30	1	SEE SPECIAL PROVISIONS FOR DETAILS
	STA 491+91.00 TO 492+76.00	57				TOTAL	1
	TOTAL	788.00					
44201383	CLASS C PATCHES, TYPE IV, 12 INCH LOCATION	SQ YD	COMMENTS	50104400	CONCRETE HEADWALL REMOVAL LOCATION	EACH	COMMENTS
	STA 317+83.43 TO 318+66.63	222			STA 465+07 LT	1	SEE SPECIAL PROVISIONS FOR DETAILS
	STA 324+39.79 TO 324+78.86	104				TOTAL	1
	STA 338+93.34 TO 339+36.65	115					
	STA 378+89.43 TO 379+24.41	93		51500100	NAME PLATES LOCATION	EACH	COMMENTS
	STA 383+65.05 TO 384+06.69	111			STA 318+25	1	Proposed SN 037-1186
	STA 393+36.66 TO 393+92.35	149			STA 339+15	1	Proposed SN 037-1188
	STA 396+81.66 TO 397+53.50	192			STA 375+32	1	Proposed SN 037-0178
	STA 462+02.20 TO 462+70.85	111			STA 393+64	1	Proposed SN 037-1187
	STA 466+09.84 TO 467+50.28	375			STA 397+17	1	Proposed SN 037-1191
	STA 479+08.85 TO 479+63.68	146			STA 466+50	1	Proposed SN 037-1192
	STA 491+91.01 TO 492+76.03	227			STA 479+36	1	Proposed SN 037-1189
	TOTAL	1845			STA 492+34	1	Proposed SN 037-1190
					TOTAL	8	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1 LOCATION	EACH	COMMENTS	54001001	BOX CULVERT END SECTIONS, CULVERT NO. 01 LOCATION	EACH	COMMENTS
	STA 318+25	1	SEE SPECIAL PROVISIONS FOR DETAILS		STA 318+25 LT	1	
	TOTAL	1				TOTAL	1
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2 LOCATION	EACH	COMMENTS	54001002	BOX CULVERT END SECTIONS, CULVERT NO. 02 LOCATION	EACH	COMMENTS
	STA 324+59	1	SEE SPECIAL PROVISIONS FOR DETAILS		STA 393+64 LT & RT	2	
	TOTAL	1			TOTAL	2	
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3 LOCATION	EACH	COMMENTS	54001003	BOX CULVERT END SECTIONS, CULVERT NO. 03 LOCATION	EACH	COMMENTS
	STA 339+23	1	SEE SPECIAL PROVISIONS FOR DETAILS		STA 466+50 LT & RT	4	
	TOTAL	1			TOTAL	4	
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4 LOCATION	EACH	COMMENTS	54001004	BOX CULVERT END SECTIONS, CULVERT NO. 04 LOCATION	EACH	COMMENTS
	STA 375+32	1	SEE SPECIAL PROVISIONS FOR DETAILS		STA 479+36 LT & RT	2	
	TOTAL	1			STA 492+34 LT & RT	2	
					TOTAL	4	
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5 LOCATION	EACH	COMMENTS	54001005	BOX CULVERT END SECTIONS, CULVERT NO. 05 LOCATION	EACH	COMMENTS
	STA 379+07	1	SEE SPECIAL PROVISIONS FOR DETAILS		STA 380+50 RT	2	See Detail on Parallel Grate
	TOTAL	1			TOTAL	2	
50100800	REMOVAL OF EXISTING STRUCTURES NO. 6 LOCATION	EACH	COMMENTS	54010603	PRECAST CONCRETE BOX CULVERTS 6' X 3' LOCATION	EQ FT	COMMENTS
	STA 383+86	1	SEE SPECIAL PROVISIONS FOR DETAILS		STA 380+50 44' RT	30	
	TOTAL	1			STA 393+64 23' LT & 23' RT @ 15° SKEW	46	
					TOTAL	76	
50100900	REMOVAL OF EXISTING STRUCTURES NO. 7 LOCATION	EACH	COMMENTS	54010906	PRECAST CONCRETE BOX CULVERTS 9' X 6' LOCATION	EQ FT	COMMENTS
	STA 393+64	1	SEE SPECIAL PROVISIONS FOR DETAILS		STA 479+36 26' LT & 22' RT	48	
	TOTAL	1			STA 492+34 50' LT & 62' RT @ 34° SKEW	112	
					TOTAL	160	
50101000	REMOVAL OF EXISTING STRUCTURES NO. 8 LOCATION	EACH	COMMENTS	54011206	PRECAST CONCRETE BOX CULVERTS 12' X 6' LOCATION	EQ FT	COMMENTS
	STA 397+12	1	SEE SPECIAL PROVISIONS FOR DETAILS		STA 466+50 39' LT & 29' RT	136	
	TOTAL	1			TOTAL	136	
50101100	REMOVAL OF EXISTING STRUCTURES NO. 9 LOCATION	EACH	COMMENTS				
	STA 462+35	1	SEE SPECIAL PROVISIONS FOR DETAILS				
	TOTAL	1					

FILE NAME :	USER NAME : hogenson, jd	DESIGNED -	REVISED -	STATE OF ILLINOIS	SCHEDULE OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
C:\pwork\pwork\cushmanbv\d016162\028889-ent-schedule.dgn		DRAWN -	REVISED -	DEPARTMENT OF TRANSPORTATION		226	3T & 3BR-1	HENRY	210	16
PLOT SCALE : 1/8" = 1'-0"		CHECKED -	REVISED -							
PLOT DATE : Wed Oct 24 11:43:33 2012		DATE -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
										ILLINOIS FED. AID PROJECT
										CONTRACT NO. 64F25