

SCHEDULE OF QUANTITIES

54011208	PRECAST CONCRETE BOX CULVERTS 12' X 8' LOCATION STA 318+25 52' LT & 50' RT	FOOT 102 <hr/> TOTAL 102	COMMENTS LOCATION TO BE DETERMINED IN THE FIELD	60100925	PIPE DRAINS 8" LOCATION STA 318+25 RT STA 324+67 RT STA 339+15 RT STA 470+09 RT STA 480+68 LT	FOOT 20 20 20 25 25 <hr/> TOTAL 110	COMMENTS LOCATION TO BE DETERMINED IN THE FIELD LOCATION TO BE DETERMINED IN THE FIELD LOCATION TO BE DETERMINED IN THE FIELD LOCATION TO BE DETERMINED IN THE FIELD
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36" LOCATION STA 397+17 59' LT & 45' RT @ 45° SKEW	FOOT 101 <hr/> TOTAL 101	COMMENTS LOCATION TO BE DETERMINED IN THE FIELD	60100935	PIPE DRAINS 10" LOCATION STA 397+17 RT STA 479+36 RT	FOOT 20 20 <hr/> TOTAL 40	COMMENTS LOCATION TO BE DETERMINED IN THE FIELD LOCATION TO BE DETERMINED IN THE FIELD
542A1093	PIPE CULVERTS, CLASS A, TYPE 2 48" LOCATION STA 339+15 32' LT & 30' RT @ 15° SKEW	FOOT 62 <hr/> TOTAL 62	COMMENTS LOCATION TO BE DETERMINED IN THE FIELD	60100955	PIPE DRAINS 15" LOCATION STA 318+25 RT	FOOT 20 <hr/> TOTAL 20	COMMENTS LOCATION TO BE DETERMINED IN THE FIELD
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15" LOCATION STA 317+00 32' LT STA 371+50 32' RT STA 373+57 36' LT STA 398+00 40' LT STA 398+25 34' RT STA 481+67 31' LT	FOOT 42 46 42 46 44 46 <hr/> TOTAL 266	COMMENTS FIELD ENTRANCE FIELD ENTRANCE FIELD ENTRANCE FIELD ENTRANCE FIELD ENTRANCE FIELD ENTRANCE	60107600	PIPE UNDERDRAINS 4" LOCATION STA 318+25 LT & RT STA 339+15 LT & RT STA 393+64 LT & RT STA 397+12 LT & RT STA 466+50 LT & RT STA 479+36 LT & RT STA 492+30 LT & RT	FOOT 115 115 58 58 58 58 58 <hr/> TOTAL 520	COMMENTS SEE DISTRICT STD. 37.2 FOR LOCATIONS SEE DISTRICT STD. 37.2 FOR LOCATIONS SEE DISTRICT STD. 37.2 FOR LOCATIONS SEE DISTRICT STD. 37.2 FOR LOCATIONS SEE DISTRICT STD. 37.2 FOR LOCATIONS SEE DISTRICT STD. 37.2 FOR LOCATIONS SEE DISTRICT STD. 37.2 FOR LOCATIONS
542D1087	PIPE CULVERTS, CLASS D, TYPE 2, 42" LOCATION STA 319+86 56' RT	FOOT 72 <hr/> TOTAL 72	COMMENTS FIELD ENTRANCE	61100500	EXPLORATION TRENCH 52" DEPTH LOCATION STA 318+25 RT STA 324+67 RT STA 339+15 RT STA 397+17 RT STA 470+09 RT STA 479+36 RT STA 480+68 RT	FOOT 150 100 150 150 100 150 100 <hr/> TOTAL 900	COMMENTS LOCATION TO BE DETERMINED IN THE FIELD LOCATION TO BE DETERMINED IN THE FIELD LOCATION TO BE DETERMINED IN THE FIELD LOCATION TO BE DETERMINED IN THE FIELD LOCATION TO BE DETERMINED IN THE FIELD LOCATION TO BE DETERMINED IN THE FIELD LOCATION TO BE DETERMINED IN THE FIELD
54213450	END SECTIONS 15" LOCATION STA 317+00 LT STA 371+50 RT STA 373+57 LT STA 398+00 LT STA 398+25 RT STA 481+67 LT	EACH 2 2 2 2 2 2 <hr/> TOTAL 12	COMMENTS LOCATION TO BE DETERMINED IN THE FIELD	61133200	FIELD TILE JUNCTION VAULTS 3' DIA. LOCATION STA 318+25 RT STA 324+67 RT STA 339+15 RT STA 397+17 RT STA 470+09 RT STA 479+36 RT STA 480+68 RT	EACH 2 1 1 1 1 1 1 <hr/> TOTAL 8	COMMENTS LOCATION TO BE DETERMINED IN THE FIELD LOCATION TO BE DETERMINED IN THE FIELD LOCATION TO BE DETERMINED IN THE FIELD LOCATION TO BE DETERMINED IN THE FIELD LOCATION TO BE DETERMINED IN THE FIELD LOCATION TO BE DETERMINED IN THE FIELD LOCATION TO BE DETERMINED IN THE FIELD
54213477	END SECTIONS 42" LOCATION STA 319+86 RT	EACH 2 <hr/> TOTAL 2	COMMENTS FIELD ENTRANCE	63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS LOCATION STA 373+95.70 TO 374+33.20 RT STA 376+30.41 TO 376+67.91 LT	FOOT 37.5 37.5 <hr/> TOTAL 75	COMMENTS LOCATION TO BE DETERMINED IN THE FIELD
54215408	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 8" LOCATION STA 324+67 RT STA 470+09 RT STA 480+68 LT	EACH 1 1 1 <hr/> TOTAL 3	COMMENTS LOCATION TO BE DETERMINED IN THE FIELD LOCATION TO BE DETERMINED IN THE FIELD LOCATION TO BE DETERMINED IN THE FIELD	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6 LOCATION STA 374+33.20 TO 374+76.95 RT STA 374+33.20 TO 374+76.95 LT STA 375+86.66 TO 376+30.41 RT STA 375+86.66 TO 376+30.41 LT	EACH 1 1 1 1 <hr/> TOTAL 4	COMMENTS LOCATION TO BE DETERMINED IN THE FIELD LOCATION TO BE DETERMINED IN THE FIELD LOCATION TO BE DETERMINED IN THE FIELD LOCATION TO BE DETERMINED IN THE FIELD
54215410	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 10" LOCATION STA 479+36 RT	EACH 1 <hr/> TOTAL 1	COMMENTS LOCATION TO BE DETERMINED IN THE FIELD	63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED LOCATION STA 373+45.70 TO 373+95.70 RT STA 373+83.20 TO 374+33.20 LT STA 376+30.41 TO 376+80.41 RT STA 376+67.91 TO 377+17.91 LT	EACH 1 1 1 1 <hr/> TOTAL 4	COMMENTS SEE DISTRICT STD. 37.2 FOR LOCATIONS SEE DISTRICT STD. 37.2 FOR LOCATIONS SEE DISTRICT STD. 37.2 FOR LOCATIONS SEE DISTRICT STD. 37.2 FOR LOCATIONS SEE DISTRICT STD. 37.2 FOR LOCATIONS
54261436	CONCRETE END SECTION, STANDARD 542001, 36", 1:4 LOCATION STA 397+17 LT	EACH 1 <hr/> TOTAL 1	COMMENTS LOCATION TO BE DETERMINED IN THE FIELD				
54261448	CONCRETE END SECTION, STANDARD 542001, 48", 1:4 LOCATION STA 339+15 LT	EACH 1 <hr/> TOTAL 1	COMMENTS LOCATION TO BE DETERMINED IN THE FIELD				
60100060	CONCRETE HEADWALL FOR PIPE DRAINS LOCATION STA 318+25 LT & RT STA 339+15 LT & RT STA 393+64 LT & RT STA 397+17 LT & RT STA 466+50 LT & RT STA 479+36 LT & RT STA 492+30 LT & RT	EACH 4 4 2 2 2 2 2 <hr/> TOTAL 18	COMMENTS SEE DISTRICT STD. 37.2 FOR LOCATIONS SEE DISTRICT STD. 37.2 FOR LOCATIONS SEE DISTRICT STD. 37.2 FOR LOCATIONS SEE DISTRICT STD. 37.2 FOR LOCATIONS SEE DISTRICT STD. 37.2 FOR LOCATIONS SEE DISTRICT STD. 37.2 FOR LOCATIONS SEE DISTRICT STD. 37.2 FOR LOCATIONS				