

80/20

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				0004 ROADWAY	0011 STRUCTURAL
51202305	DRIVING PILES	FOOT	2,045		2,045
51203600	TEST PILE STEEL HP12X53	EACH	4		4
51203800	TEST PILE STEEL HP14X73	EACH	2		2
51500100	NAME PLATES	EACH	1		1
51602000	PERMANENT CASING	FOOT	60		60
51603000	DRILLED SHAFT IN SOIL	CU YD	110.7		110.7
51604000	DRILLED SHAFT IN ROCK	CU YD	48.4		48.4
52000110	PREFORMED JOINT STRIP SEAL	FOOT	86.5		86.5
52000212	FINGER PLATE EXPANSION JOINT, 4"	FOOT	41		41
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	6		6
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	18		18
52100520	ANCHOR BOLTS, 1"	EACH	108		108
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2	2	
54010704	PRECAST CONCRETE BOX CULVERTS 7' X 4'	FOOT	90	90	

NOTES:  
 \* SPECIALTY ITEM