

SUMMARY OF QUANTITIES

| CODE NUMBER | ITEM DESCRIPTION | UNIT | TOTAL QTY. | PEORIA COUNTY | PEORIA COUNTY | TAZEWELL COUNTY |
|-------------|--|------|------------|--|---|---|
| | | | | CONST. TYPE CODE 0021 90% STATE 10% CITY TRAFFIC SIGNALS URBAN | CONST. TYPE CODE 0021 100% STATE OVERHEAD LIGHTING URBAN | CONST. TYPE CODE 0021 100% STATE OVERHEAD LIGHTING URBAN |
| 87700320 | STEEL MAST ARM ASSEMBLY AND POLE, 55 FT. | EACH | 3.0 | 3.0 | | |
| 87700420 | STEEL MAST ARM ASSEMBLY AND POLE, 70 FT. | EACH | 1.0 | 1.0 | | |
| 87800415 | CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER | FOOT | 45.0 | 45.0 | | |
| 87800420 | CONCRETE FOUNDATION, TYPE E, 42-INCH DIAMETER | FOOT | 21.0 | 21.0 | | |
| 87900100 | DRILL EXISTING FOUNDATION | EACH | 3.0 | 3.0 | | |
| 87900200 | DRILL EXISTING HANDHOLE | EACH | 3.0 | 3.0 | | |
| 88030020 | SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED | EACH | 5.0 | 5.0 | | |
| 88030050 | SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED | EACH | 2.0 | 2.0 | | |
| 88030070 | SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED | EACH | 3.0 | 3.0 | | |
| 88030080 | SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED | EACH | 5.0 | 5.0 | | |
| 88030100 | SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED | EACH | 1.0 | 1.0 | | |
| 88200310 | TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC | EACH | 10.0 | 10.0 | | |
| 89500200 | RELOCATE EXISTING PEDESTRIAN SIGNAL HEAD | EACH | 7.0 | 7.0 | | |
| 89500400 | RELOCATE EXISTING PEDESTRIAN PUSH-BUTTON | EACH | 7.0 | 7.0 | | |
| 89502210 | MODIFY EXISTING CONTROLLER CABINET | EACH | 1.0 | 1.0 | | |
| 89502375 | REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT | EACH | 1.0 | 1.0 | | |
| 89502385 | REMOVE EXISTING CONCRETE FOUNDATION | EACH | 4.0 | 4.0 | | |
| X0325924 | CLEAN, RELAMP AND MAINTENANCE OF EXISTING LUMINAIRE | EACH | 110.0 | | 102.0 | 8.0 |
| X0326812 | CAT 5 ETHERNET CABLE | FOOT | 261.5 | 261.5 | | |
| X0327905 | CLOSED CIRCUIT TELEVISION DOME CAMERA, IP BASED (INSTALL ONLY) | EACH | 1.0 | 1.0 | | |