

CONTRACT NO. 72501

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				80% FEDERAL 20% STATE	80% FED 20% ST	80% FED 20% ST	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 15% STATE 5% CITY	80% FEDERAL 20% CITY	80% STATE 20% TOWNSHIP			
				ROADWAY/ STORM SEWER	SIDEWALK CITY	CAPITAL TOWNSHIP SIDEWALK	TRAFFIC SIGNALS ELM	TRAFFIC SIGNALS RIDGE	BIKE LANES CITY	BIKE LANES CAPITAL TOWNSHIP			
				0003 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0028 URBAN	0028 URBAN			
M6060500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30	METER	1138.9	1138.9									
M6060700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60	METER	409.2	409.2									
M6061600	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-22.60	METER	30.9	30.9									
M6690100	BACKFILL PLUGS	CU M	20.0	20.0									
M6690200	NON-SPECIAL WASTE DISPOSAL	CU M	8000.0	8000.0									
* M7200200	SIGN PANEL - TYPE 2	SO M	2.1				2.1						
* M7800200	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	93	93									
* M7800350	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SO M	89	89									
* M7800360	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 125MM	METER	735	735									
* M7800390	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 600MM	METER	113	113									
* M7809125	MODIFIED URETHANE PAVEMENT MARKING - LINE 125MM	METER	7442	7442									
* M7809150	MODIFIED URETHANE PAVEMENT MARKING - LINE 150MM	METER	1081	1081									
* M7809200	MODIFIED URETHANE PAVEMENT MARKING - LINE 200MM	METER	47	47									
* M7809300	MODIFIED URETHANE PAVEMENT MARKING - LINE 300MM	METER	32	32									
M7830100	PAVEMENT MARKING REMOVAL	SO M	387.0	387.0									

1

*SPECIALTY ITEM

1 REV. 10/31/13

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.P. ROUTE 668 (DIRKSEN PARKWAY)
SECTION 28R-1
SANGAMON COUNTY
SCALE: NONE
DATE: 06/2013
DRAWN BY: GE
CHECKED BY: FML