

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
668	28R-1	SANGAMON	354	18

CONTRACT NO. 72501

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				80% FEDERAL 20% STATE	80% FED 20% ST	80% FED 20% ST	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 15% STATE 5% CITY	80% FEDERAL 20% CITY	80% STATE 20% TOWNSHIP			
				ROADWAY/ STORM SEWER	SIDEWALK CITY	CAPITAL TOWNSHIP SIDEWALK	TRAFFIC SIGNALS ELM	TRAFFIC SIGNALS RIDGE	BIKE LANES CITY	BIKE LANES CAPITAL TOWNSHIP			
				0003 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0028 URBAN	0028 URBAN			
*MX030457	STORM SEWER (WATER MAIN REQUIREMENTS) TYPE 1, 375MM	METER	13.0	13.0									
*MX030579	STORM SEWER (WATER MAIN REQUIREMENTS) TYPE 2, 375MM	METER	133.0	133.0									
*MX032178	TEMPORARY INFORMATION SIGNING	SO M	300	300									
MX032200	ENGINEERED BARRIER	SO M	125	125									
MX440050	ISLAND PAVEMENT REMOVAL	SO M	102	102									
MX440950	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ M	23559	23559									
MX606360	COMBINATION CONCRETE CURB AND GUTTER, TYPE B (SPECIAL)	METER	46.9	46.9									
*MX783072	GROOVING FOR RECESSED PAVEMENT MARKING 152MM	METER	7442	7442									
*MX783074	GROOVING FOR RECESSED PAVEMENT MARKING 178MM	METER	1081	1081									
*MX783076	GROOVING FOR RECESSED PAVEMENT MARKING 229MM	METER	47	47									
*MX783078	GROOVING FOR RECESSED PAVEMENT MARKING 330MM	METER	32	32									
MX871055	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	METER	1895.5				1389.3	506.2					
X0322936	REMOVE EXISTING FLARED END SECTION	EACH	9	9									
X0326820	INLETS, SPECIAL, TYPE E, 4' X 4'	EACH	8	8									



14

*SPECIALTY ITEM

Rev. 10/31/13

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.P. ROUTE 668 (DIRKSEN PARKWAY)
SECTION 28R-1
SANGAMON COUNTY
SCALE: NONE
DATE: 06/2013
DRAWN BY: GE
CHECKED BY: FML