

DELINEATORS						
LOCATION			LT/RT	DELINEATORS SINGLE	DELINEATORS DOUBLE	DELINEATORS REMOVAL
STA.	TO	STA.		(EACH)	(EACH)	(EACH)
I-64 EASTBOUND						
87+58	TO	119+78	RT	11		11
124+08	TO	128+12	RT	3		3
140+35	TO	192+44	RT	22		22
199+05	TO	209+06	RT	6		6
224+24	TO	244+71	RT	5		5
I-64 WESTBOUND						
87+46	TO	97+27	LT	6		6
102+04	TO	106+85	LT	1		1
113+33	TO	129+19	LT	7		7
138+62	TO	192+51	LT	24		24
212+94	TO	221+00	LT	2		2
224+81	TO	245+33	LT	5		5
18TH ST RAMP "F"						
404+77	TO	408+38	RT	4		4
404+77	TO	408+38	LT	4		4
408+38	TO	413+48	LT		10	10
25TH ST RAMP "H"						
1+33	TO	8+17	RT	7		7
8+17	TO	12+62	RT		8	8
1+33	TO	8+17	LT	7		7
25TH ST RAMP "K"						
4+59	TO	8+23	RT	4		4
4+59	TO	8+23	LT	4		4
8+23	TO	12+42	LT		8	8
25TH ST RAMP "G"						
0+00	TO	4+28	RT		8	8
4+28	TO	7+69	RT	7		7
4+28	TO	7+50	LT	6		6
25TH ST RAMP "J"						
4+5	TO	12+29	RT	24		24
12+29	TO	18+91	RT		14	14
9+21	TO	12+29	LT	6		6
IL 111 RAMP "A"						
9+20	TO	22+68	RT	13		13
4+05	TO	9+20	LT		26	26
IL 111 RAMP "B"						
11+26	TO	15+07	RT		8	8
21+54	TO	24+40	RT	6		6
15+07	TO	19+39	LT	8		8
IL 111 RAMP "C"						
12+29	TO	21+75	RT		18	18
4+05	TO	12+29	LT	23		23
IL 111 RAMP "D"						
0+00	TO	6+28	RT		12	12
10+10	TO	17+87	RT	10		10
6+28	TO	10+10	LT	7		7
IL 111 RAMP "E"						
11+26	TO	20+52	RT		18	18
3+95	TO	11+90	LT	20		20
IL 111 RAMP "F"						
10+91	TO	17+44	RT		14	14
4+05	TO	6+61	LT	6		6
6+61	TO	10+91	LT	4		4
SUBTOTAL:				262	144	406
TOTAL:					406	406

SURFACE REMOVAL BUTT- JOINT			
STA	TO	STA	(SQ YD)
I-64 EASTBOUND			
89+03.37	TO	89+43.37	267
94+05.93	TO	94+45.93	293
96+19.47	TO	96+59.47	240
97+51.11	TO	97+91.11	240
100+62.55	TO	101+02.55	240
104+39.82	TO	104+79.82	240
106+55.23	TO	106+95.23	240
119+46.49	TO	119+86.49	240
121+69.35	TO	122+09	276
132+46.	TO	132+86	293
140+35	TO	140+75	240
157+49	TO	157+89	240
158+97.97	TO	159+37.97	240
244+31	TO	244+70.66	293
I-64 WESTBOUND			
88+91.55	TO	89+31.55	240
93+26.41	TO	93+66.41	240
95+46.98	TO	95+86.98	240
97+59.85	TO	97+99.85	267
100+72.52	TO	101+12.52	240
104+49.74	TO	104+89.74	240
106+65.15	TO	107+05.15	240
119+64.88	TO	120+04.88	240
121+82.72	TO	122+23	240
130+71.	TO	131+11	240
138+62.48	TO	139+02.48	240
157+38.41	TO	157+78.41	240
158+87.08	TO	159+27.08	240
244+92.45	TO	245+32.45	293
18TH ST RAMP "F"			
404+77	TO	405+17	116
25TH ST RAMP "H"			
1+33	TO	1+73	116
25TH ST RAMP "K"			
1+17	TO	1+57	151
25TH ST RAMP "G"			
7+09.04	TO	7+49.04	116
8+97.4	TO	9+37.4	116
15+15.	TO	15+55.	116
25TH ST RAMP "J"			
4+5	TO	+85.	116
7+36	TO	7+76.02	116
9+24.11	TO	9+64.11	116
IL 111 RAMP "A"			
4+05	TO	4+45	116
IL 111 RAMP "B"			
25+17	TO	25+57	116
IL 111 RAMP "C"			
4+05	TO	4+45	116
IL 111 RAMP "D"			
17+47	TO	17+87	151
IL 111 RAMP "E"			
3+95	TO	4+35	116
IL 111 RAMP "F"			
4+05	TO	4+45	116
TOTAL:			8827

TEMPORARY RAMPS			
LOCATION			AREA
STA	TO	STA	(SQ YD)
I-64 EASTBOUND			
89+03.37	TO	89+43.37	37
94+34.93	TO	94+45.93	40
96+19.47	TO	96+30.47	33
97+80.11	TO	97+91.11	33
100+62.55	TO	100+73.55	33
104+68.82	TO	104+79.82	33
106+55.23	TO	106+66.23	33
119+75.49	TO	119+86.49	33
121+69.35	TO	121+80	38
132+75.	TO	132+86	40
140+35	TO	140+46	33
157+78	TO	157+89	33
158+97.97	TO	159+08.97	33
244+60	TO	244+70.66	40
I-64 WESTBOUND			
88+91.55	TO	89+02.55	33
93+55.41	TO	93+66.41	33
95+46.98	TO	95+57.98	33
97+88.85	TO	97+99.85	37
100+72.52	TO	100+83.52	33
104+78.74	TO	104+89.74	33
106+65.15	TO	106+76.15	33
119+93.88	TO	120+04.88	33
121+82.72	TO	121+94	33
131+00.	TO	131+11	33
138+62.48	TO	138+73.48	33
157+67.41	TO	157+78.41	33
158+87.08	TO	158+98.08	33
245+21.45	TO	245+32.45	40
18TH ST RAMP "F"			
404+77	TO	404+88	16
25TH ST RAMP "H"			
1+33	TO	1+44	16
25TH ST RAMP "K"			
1+17	TO	1+28	21
25TH ST RAMP "G"			
7+38.04	TO	7+49.04	16
8+97.4	TO	9+08.4	16
15+44.	TO	15+55.	16
25TH ST RAMP "J"			
4+5	TO	+56.	16
7+65	TO	7+76.02	16
9+24.11	TO	9+35.11	16
IL 111 RAMP "A"			
4+05	TO	4+16	16
IL 111 RAMP "B"			
25+46	TO	25+57	16
IL 111 RAMP "C"			
4+05	TO	4+16	16
IL 111 RAMP "D"			
17+76	TO	17+87	21
IL 111 RAMP "E"			
3+95	TO	4+06	16
IL 111 RAMP "F"			
4+05	TO	4+16	16
TOTAL:			1214

RIPRAP					
LOCATION			STONE RIPRAP CLASS A2	FILTER FABRIC	REMOVE EXISTING RIPRAP
STA.	TO	STA.	(SQYD)	(SQYD)	(SQYD)
I-64 MEDIAN					
89+10	TO	93+95	1129	1129	1129
95+97	TO	97+84	460	460	460
100+80	TO	104+75	907	907	907
106+70	TO	119+85	2961	2961	2961
121+87	TO	126+15	1051	1051	
128+75	TO	133+32	1076	1076	
138+16	TO	147+85	2451	2451	
149+90	TO	157+75	2065	2065	
158+97	TO	163+75	1278	1278	
195+25	TO	213+00	4391	4391	
232+22	TO	244+93	3326	3326	
TOTAL:			21093	21093	5456

REMOVE HIGH TENSION CABLE MEDIAN BARRIER				
LOCATION			REMOVE HIGH TENSION CABEL MEDIAN BARRIER	REMOVE HIGH TENSION CABLE MEDIAN BARRIER TERMINAL
STATION			(FOOT)	(EACH)
I-64 EASTBOUND				
106+80	TO	119+91	1211	2
159+05	TO	202+09	4204	2
I-64 WESTBOUND				
150+12.77	TO	151+17.75	4.98	2
200+57	TO	245+06	4349	2
TOTAL			9769	8

HIGH TENSION CABLE MEDIAN BARRIER				
LOCATION			HIGH TENSION CABLE MEDIAN BARRIER	HIGH TENSION CABLE MEDIAN BARRIER TERMINALS
STA	TO	STA	(FOOT)	(EACH)
I-64 EASTBOUND				
163+86.50	TO	164+36.50		1
164+36.50	TO	194+65.00	3029	
194+65.00	TO	195+15.00		1
I-64 WESTBOUND				
213+10.00	TO	213+60.00		1
213+60.00	TO	231+62.00	1802	
231+62.00	TO	232+12.00		1
TOTAL:			4830.5	4