

90% FED.
10% STATE
URBAN

SUMMARY OF QUANTITIES

90% FED.
10% STATE
URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		0004	0014
20200100	EARTH EXCAVATION	CU YD	6302	6302	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	690	690	
28000305	TEMPORARY DITCH CHECKS	FOOT	4009.5	4009.5	
28000500	INLET AND PIPE PROTECTION	EACH	6	6	
28100103	STONE RIPRAP, CLASS A2	SO YD	21093	21093	
28100107	STONE RIPRAP, CLASS A4	SO YD	964	964	
28200200	FILTER FABRIC	SO YD	21093	21093	
35100100	AGGREGATE BASE COURSE, TYPE A	TON	9439	9439	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	576.3	576	0.3
40600300	AGGREGATE (PRIME COAT)	TON	921	921	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	8827	8827	
40600990	TEMPORARY RAMP	SO YD	1214	1214	
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	16798	16798	
40603243	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90	TON	19192	19192	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		0004	0014
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	61	61	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	69138	68413	725
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SO YD	142989	142989	
44000169	HOT-MIX ASPHALT SURFACE REMOVAL, 5"	SO YD	6994	6994	
44004250	PAVED SHOULDER REMOVAL	SO YD	13813		13813
44200994	CLASS B PATCHES, TYPE II, 12 INCH	SO YD	123	123	
44200998	CLASS B PATCHES, TYPE III, 12 INCH	SO YD	74	74	
44201000	CLASS B PATCHES, TYPE IV, 12 INCH	SO YD	373	373	
44201011	CLASS B PATCHES, TYPE III, 13 INCH	SO YD	55	55	
44201013	CLASS B PATCHES, TYPE IV, 13 INCH	SO YD	37	37	
44201299	DOWEL BARS 1 1/2"	EACH	893	893	
44213100	PAVEMENT FABRIC	SO YD	538	538	
44213200	SAW CUTS	FOOT	3202	3202	
44213204	TIE BARS 3/4"	EACH	94	94	

Rev.

FILE NAME	USER NAME	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
76022-ehf-plandgn	burnsideen	DRAWN	REVISED			64	B2-(1,2,3,4RS-1)	ST. CLAIR	208	4	
PLOT SCALE - 100,0000 1/4" = 1'		CHECKED	REVISED			SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT
PLOT DATE - 8/25/2013		DATE	REVISED							CONTRACT NO. 76022	