

# SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0040					
				20% STATE	80% FEDERAL				
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	21	21					
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1					
70106700	TEMPORARY RUMBLE STRIPS	EACH	6	6					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	150	150					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2253	2253					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	801	801					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	400	400					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	375	375					
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2					
70600350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2253	2253					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	751	751					
X4404260	PAVED SHOULDER REMOVAL (SPECIAL)	SQ YD	54	54					

\*SPECIALTY ITEM