



PLAN

INSIDE FACE OF NORTH CURB/PARAPET

Location	Station	Offset	Theoretical Grade Elevations
W. end appr. slab	912+70.50	-16.42	353.37
a	912+80.50	-16.42	353.41
b	912+90.50	-16.00	353.46
E. end appr. Slab	913+00.50	-16.00	353.50

STAGE CONSTRUCTION LINE

Location	Station	Offset	Theoretical Grade Elevations
W. end appr. slab	912+70.50	0.50	353.64
a	912+80.50	0.50	353.68
b	912+90.50	0.50	353.72
E. end appr. Slab	913+00.50	0.50	353.76

NORTH EDGE OF ROADWAY

Location	Station	Offset	Theoretical Grade Elevations
W. end appr. slab	912+70.50	-12.00	353.46
a	912+80.50	-12.00	353.50
b	912+90.50	-12.00	353.54
E. end appr. Slab	913+00.50	-12.00	353.58

SOUTH EDGE OF ROADWAY

Location	Station	Offset	Theoretical Grade Elevations
W. end appr. slab	912+70.50	12.00	353.46
a	912+80.50	12.00	353.50
b	912+90.50	12.00	353.54
E. end appr. Slab	913+00.50	12.00	353.58

ROADWAY & PROFILE GRADE

Location	Station	Offset	Theoretical Grade Elevations
W. end appr. slab	912+70.50	0.00	353.65
a	912+80.50	0.00	353.69
b	912+90.50	0.00	353.73
E. end appr. Slab	913+00.50	0.00	353.77

INSIDE FACE OF SOUTH CURB/PARAPET

Location	Station	Offset	Theoretical Grade Elevations
W. end appr. slab	912+70.50	16.42	353.37
a	912+80.50	16.42	353.41
b	912+90.50	16.00	353.46
E. end appr. Slab	913+00.50	16.00	353.50

PRINT DRIVER = L:\05-ESCA\PLT  
 MAKE NAME = 8/2/2013 11:36:43 AM  
 FILE NAME = 8/2/2013 11:36:43 AM



USER NAME = has	DESIGNED - SHL 12/12	REVISED -
ESCA PROJECT NO. 988.12	CHECKED - RDP 03/13	REVISED -
PLOT SCALE = 0.2" = 1' / IN.	DRAWN - HAS 12/12	REVISED -
PLOT DATE = 8/2/2013 11:36:43 AM	CHECKED - RDP 03/13	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

TOP OF WEST APPROACH SLAB ELEVATIONS  
 STRUCTURE NO. 076-0032

SHEET NO. 6 OF 21 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
885	112B-1	POPE	56	28
CONTRACT NO. 78230			ILLINOIS FED. AID PROJECT AID	