



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 31, 2019

SUBJECT: PARK ROAD
Section LAKE AQUA NA 2018
Stephenson County
Contract No. 46906
Item No. 60, November 8, 2019 Letting
Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Table of Contents to the Special Provisions.
2. Revised page 1 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

TABLE OF CONTENTS

| | |
|--|----|
| LOCATION OF PROJECT | 1 |
| DESCRIPTION | 1 |
| WORKING DAYS (BDE)..... | 1 |
| TRAFFIC CONTROL PLAN | 2 |
| TRAFFIC CONTROL AND PROTECTION (SPECIAL)..... | 4 |
| CONSTRUCTION COORDINATION WITH SITE OPERATIONS..... | 5 |
| TREE REMOVAL..... | 5 |
| ABANDON AND FILL EXISTING SANITARY SEWER..... | 6 |
| AGGREGATE SURFACE COURSE, TYPE B SPECIAL..... | 6 |
| BACKFLOW PREVENTER AND ENCLOSURE..... | 7 |
| COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (VARIABLE WIDTH GUTTER FLAG)..... | 9 |
| CONCRETE ISLAND (SPECIAL)..... | 10 |
| CONCRETE REMOVAL (SPECIAL) | 10 |
| CONCRETE WALL REMOVAL..... | 11 |
| DOUBLE INLET, SPECIAL | 11 |
| FILLING EXISTING WELLS..... | 12 |
| GRANULAR CULVERT BACKFILL..... | 12 |
| HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH | 13 |
| MANHOLES, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID..... | 13 |
| MINOR SIGN COMPLETE..... | 14 |
| PAVEMENT REMOVAL (SPECIAL)..... | 15 |
| PIPE CULVERT REMOVAL..... | 15 |
| PORTLAND CEMENT CONCRETE SIDEWALK CURB | 16 |
| PRAIRIE SEEDING (SPECIAL) | 17 |
| PRECAST CONCRETE PARKING BLOCK | 18 |
| REMOVE AND RE-ERECT EXISTING SIGN..... | 19 |
| REMOVE EXISTING GATE | 19 |
| REMOVE EXISTING PARKING BLOCKS..... | 19 |
| REMOVE EXISTING RIPRAP | 20 |
| REMOVE WOOD POST | 20 |
| ROCKFILL – FOUNDATION | 21 |
| SANITARY MANHOLES TO BE REMOVED..... | 22 |

SANITARY SEWER 4"22

SAW CUTS22

SEEDING (SPECIAL)23

SIGN REMOVAL.....24

SIGN SUPPORT SPECIAL24

SPECIAL GRATE NO. 125

STUMP REMOVAL ONLY25

TIMBER SIDEWALK REMOVAL AND REPLACEMENT25

TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH26

TRAFFIC BARRIER TERMINAL, TYPE 126

TUBULAR STEEL GATE27

WATER HYDRANT.....28

WATER SERVICE LINE, SPECIAL.....28

WATER TOWER (FREEZE PROOF).....29

WATER VALVE 1" OR 1 ½"29

WOOD GUARDRAIL REMOVAL30

ELECTRIC SERVICE INSTALLATION, SPECIAL.....31

REMOVE ELECTRIC SERVICE31

REMOVE EXISTING POWER PEDESTAL32

TRANSFORMER PLATFORM32

CONCRETE SIDEWALK SALVAGE32

LIGHT POLE, SPECIAL, 30'32

LUMINAIRE, LED, ROADWAY, OUTPUT DESIGNATION E33

LUMINAIRE PERFORMANCE TABLE.....34

HOT-MIX ASPHALT MIXTURE IL-9.5FG (CBM).....35

HOT-MIX ASPHALT - DENSITY TESTING OF LONGITUDINAL JOINTS (BDE).....38

HOT-MIX ASPHALT – OSCILLATORY ROLLER (BDE)39

RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (BDE).....41

STORM WATER POLLUTION PREVENTION PLAN.....52

ACOE PERMIT62

MEMBRANE WATERPROOFING SYSTEM FOR BURIED STRUCTURES108

BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE).....110

COMPENSABLE DELAY COSTS (BDE)112

CONCRETE MIX DESIGN – DEPARTMENT PROVIDED (BDE).....116

| | |
|---|-----|
| DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) | 116 |
| DISPOSAL FEES (BDE)..... | 127 |
| EMULSIFIED ASPHALTS (BDE) | 128 |
| EQUIPMENT PARKING AND STORAGE (BDE) | 131 |
| FUEL COST ADJUSTMENT (BDE) | 132 |
| HOT MIX ASPHALT – QUALITY CONTROL FOR PERFORMANCE (BDE) | 135 |
| LIGHTS ON BARRICADES (BDE)..... | 141 |
| LUMINAIRES, LED (BDE) | 142 |
| MANHOLES, VALVE VAULTS, AND FLAT SLAB TOPS (BDE) | 153 |
| PAYMENTS TO SUBCONTRACTORS (BDE) | 154 |
| PORTLAND CEMENT CONCRETE (BDE) | 154 |
| PROGRESS PAYMENTS (BDE)..... | 155 |
| REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE) | 156 |
| SILT FENCE, GROUND STABILIZATION AND RIPRAP FILTER FABRIC (BDE) | 168 |
| STEEL COST ADJUSTMENT (BDE) | 170 |
| STEEL PLATE BEAM GUARDRAIL MANUFACTURING (BDE) | 172 |
| SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) | 173 |
| SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)..... | 173 |
| TRAFFIC CONTROL DEVICES - CONES (BDE)..... | 174 |
| WARM MIX ASPHALT (BDE) | 175 |
| WEEKLY DBE TRUCKING REPORTS (BDE)..... | 177 |

STATE OF ILLINOIS

SPECIAL PROVISIONS

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction" adopted April 1, 2016, the latest edition of the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways", and the Manual of Test Procedures for Materials" in effect on the date of invitation for bids, and the "Supplemental Specifications and Recurring Special Provisions" indicated on the Check Sheet included herein which apply to and govern the construction of Park Road, Section LAKE LE-AQUA-NA 2018, Stephenson County, Contract No. 46906 and in case of conflict with any part or parts of said specifications, the said Special Provisions shall take precedence and shall govern.

LOCATION OF PROJECT

The project limits are within the Lake Le-Aqua-Na State Park, located at 854 North Lake Road, Lena, IL in Stephenson County.

DESCRIPTION

This proposed improvement consists of the asphalt resurfacing and reconstruction of the park roads and parking lots, removal and replacement of culverts, removal and replacement of some electrical components, pavement marking, ADA sidewalk/ramp upgrades, and all other necessary work to complete the project within the Lake Le-Aqua-Na State Park in Stephenson County.

WORKING DAYS (BDE)

Effective: January 1, 2002

The Contractor shall complete the work within **95** working days.