

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				100% STATE	
				ROADWAY 0005	MINOR STRUCTURES 0004
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,514	1,514	0
40600990	TEMPORARY RAMP	SQ YD	111	111	0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	10,087	10,087	0
40700100	BITUMINOUS MATERIALS (TACK COAT)	POUND	106,227	106,227	0
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	48	48	0
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	2,205	2,205	0
* 42400800	DETECTABLE WARNINGS	SQ FT	40	40	0
44000100	PAVEMENT REMOVAL	SQ YD	1,784	1,784	0
44000600	SIDEWALK REMOVAL	SQ FT	1,021	1,021	0
44201692	CLASS D PATCHES, TYPE II, 4 INCH	SQ YD	56	56	0
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	848	848	0
50105220	PIPE CULVERT REMOVAL	FOOT	106	106	0
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1,801	0	1,801
50700105	TREATED TIMBER	F.B.M.	58	0	58

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				100% STATE	
				ROADWAY 0005	MINOR STRUCTURES 0004
50700305	HARDWARE	POUND	43	0	43
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	96	96	0
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	40	40	0
542A0223	PIPE CULVERTS, CLASS A, TYPE 1, 18"	FOOT	40	40	0
54248510	CONCRETE COLLAR	CU YD	1	1	0
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	6	6	0
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	4	4	0
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	2	0
54262712	METAL FLARED END SECTIONS 12"	EACH	2	2	0
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	5	5	0
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	175	175	0
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	8.9	0	8.9
* 67100100	MOBILIZATION	L SUM	1	1	0
* 72000100	SIGN PANEL - TYPE 1	SQ FT	604	604	0
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	144	144	0

* PAY ITEMS WITH SPECIAL PROVISION

PEN TABLE: DOTSSZ_Standard Project Pen.tbl
 DRIVER: JGG
 SHEET: 1/20/19
 FILE: I:\2019\10\18\17209 - IOT PTB 186-013 Kickapoo Road\104_Drawing\DOT\CONC\DOT_Sheet\018017705_004_SQD_02.dgn



USER NAME = jgr/mm	DESIGNED - JGG	REVISED
PLOT SCALE = 2,000' / 1" = 8/23/2019 5:22:01 PM	DRAWN - SRL	REVISED
	CHECKED - GAC	REVISED
	DATE - 08/23/19	REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
KICKAPOO STATE PARK

SCALE: SHEET 2 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	KICKAPOO 2019	VERMILION	89	4
ILLINOIS FED. AID PROJECT			CONTRACT NO. 46909	

REV. 10/28/19 REV. 10/1/19

LOCATION	AGGREGATE				
	AGGREGATE BASE COURSE, TYPE B 4"	AGGREGATE BASE COURSE, TYPE B 6"	AGGREGATE BASE REPAIR	AGGREGATE SURFACE COURSE, TYPE B	AGGREGATE WEDGE SHOULDER, TYPE B
DESCRIPTION	35101600 SQ YD	35101800 SQ YD	35800200 TON	40200800 TON	48102100 TON
FAIRGROUNDS CONNECTOR ROAD		265	27		7
KICKAPOO PARK RD WEST OF SN 092-9903 (BRIDGE OVER VERMILION RIVER)					18
KICKAPOO PARK RD FROM SN 092-9903 (BRIDGE OVER VERMILION RIVER) TO NORTHBOUND KICKAPOO PARK RD					34
SKYLINE DR FROM NB KICKAPOO PARK RD TO SKYLINE #1 PARKING PULLOFF					67
SKYLINE DR FROM SKYLINE #1 PARKING PULLOFF TO SN 092-0127 (I-74)					57
SKYLINE DR FROM SN 092-0127 (I-74) TO SN 092-9904					35
N 1180 EAST RD FROM SKYLINE DR TO LITTLE NOOK FISHING AREA PARKING LOT					59
N 1180 EAST RD FROM LITTLE NOOK FISHING AREA PARKING LOT TO KICKAPOO PARK RD					77
N 1180 EAST RD FROM KICKAPOO PARK RD TO CLEAR POND BOAT RAMP PARKING LOT					24
HIGH POND & NO NAME POND ACCESS ROAD					25
HIGH POND & NO NAME POND PARKING AREAS				66	1
KICKAPOO PARK RD FROM SKYLINE DR TO PARK LIMITS (CR1900 N)					61
EMERALD AND INLAND SEA DAY USE ACCESS ROAD					61
DOUGHNUT LAKE				762	
CANOE LAUNCH RAMP	53	203			
IRONWOOD DAY USE AREA		1063			6
WHITETAIL-WALNUT DAY USE AREA					25
PAVILION DAY USE AREA		591			5
PEELMAN POND		11		2	
CONCESSIONS AREA PARKING LOT		3712	60	147	
CLEAR POND BOAT RAMP PARKING LOT		151			1
PARK OFFICE PARKING LOT		305			
SKYLINE DRIVE PARKING PULLOFF #3		157			
SPORTSMANS LAKE					
SPORTSMAN LAKE BOAT RAMP		165			
PARKING PULLOFF SPORTSMAN #1		314			
SPORTSMAN LAKE PARKING LOT #2		551			7
SPORTSMAN LAKE PARKING LOT #2 TRAIL				20	

LOCATION	AGGREGATE					
	AGGREGATE BASE COURSE, TYPE B 4'	AGGREGATE BASE COURSE, TYPE B 6"	AGGREGATE BASE REPAIR	AGGREGATE SURFACE COURSE, TYPE B	AGGREGATE WEDGE SHOULDER, TYPE B	
DESCRIPTION	35101600 SQ YD	35101800 SQ YD	35800200 TON	40200800 TON	48102100 TON	
EMERALD POND AND INLAND SEA PARKING LOTS		145			20	
MOUNTAIN BIKE TRAIL HEAD		524	159	1		
CAMP ROAD	STA. 10+12.83 TO 27+11.11				48	
MIAMI CAMPGROUND RD	STA. 27+11.11 TO 55+82.01 LOTS 1-39, 41-42, 45-58, 60		41		71	
ILLINI CAMPGROUND RD	STA. 100+00.00 TO 112+87.84 LOTS 61-71, 74-84, 86			274	32	
FOX CAMPGROUND RD	STA. 200+00.00 TO 221+84.15 LOTS 95-98, 100-101		23		54	
ERIE CAMPGROUND ROAD	STA. 300+00.00 TO 306+12.51 STA. 306+12.51 TO 320+50.91 STA. 400+00.00 TO 403+24.96 STA. 500+00.00 TO 502+46.25 PARKING AREA LOTS 120R-153R			222 43 33 11 164	15	
SAUK CAMPGROUND ROAD	STA. 600+00.00 TO 611+90.40			176		
RED EAR CAMPGROUND ROAD	STA. 1000+74.50 TO 1015+63.28 STA. 2000+00.00 TO 2002+24.64 STA. 3000+00.00 TO 3003+86.40 PARKING AREA			256 37 50 46		
DUMP STATION ROAD	STA. 700+00.00 TO 703+36.50				24	
SHOWER DRIVE	STA. 800+00.00 TO 802+73.89				7	
AMPHITHEATRE DRIVE	STA. 900+00.00 TO 902+77.16				7	
HUNTING LOTS	LOT 1 LOT 5 LOT 6 LOT 7 LOT 8 LOT 9 LOT 10 LOT 11 LOT 12 LOT 13 LOT 14 JOHNSON HILL CEMETERY			60 38 41 39 41 85 65 68 36 32 40 50		
TOTAL		53	8,221	246	3,636	848

AGGREGATE NOTES:
1. AGGREGATE SURFACE COURSE, TYPE B, SHALL BE CM 16 FOR CAMPSITES AND CA 6 OR 10 FOR ROADWAYS.



PEN TABLE: IDO ISSA Stencil Project Pen, 2H
 FILE: 17706_CAD_Plan_100%_DWG.dwg
 SHEET: 08/23/2019 11:23:00 AM - E:\17706_CAD_Plan_100%_DWG.dwg
 PLOT DATE: 10/30/2019 8:18:47 AM



USER NAME - jgr/mm	DESIGNED - JGG	REVISED - 10/30/19
PLOT SCALE - 2,000' = 1" IN	DRAWN - SRL	REVISED
PLOT DATE - 10/30/2019	CHECKED - GAC	REVISED
	DATE - 08/23/19	REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES
KICKAPOO STATE PARK

SCALE: SHEET 8 OF 15 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	KICKAPOO 2019	VERMILION	89	14
ILLINOIS FED. AID PROJECT			CONTRACT NO. 46909	