


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	STP(M)	CMAQ(CMM)			STP(M)
				CONSTRUCTION CODE				
				80% FED 20% STATE ROADWAY	80% FED 13.4% STATE 6.6% COUNTY SIGNALS	80% FED 20% STATE INTERCONNECT	80% FED 20% STATE RET WALL	100% FPD + EVP
				0004 URBAN	0021 URBAN	0021 URBAN	0040 URBAN	0021 URBAN
28000400	PERIMETER EROSION BARRIER	FOOT	2010	2010				
28000510	INLET FILTERS	EACH	14	14				
28001100	TEMPORARY EROSION CONTROL BLANKET	SO YD	1115	1115				
28100107	STONE RIPRAP, CLASS A4	SO YD	21				21	
28200200	FILTER FABRIC	SO YD	21				21	
30300112	AGGREGATE SUBGRADE IMPROVEMENT, 12"	SO YD	4385	4385				
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SO YD	16	16				
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	675	675				
35501309	HOT-MIX ASPHALT BASE COURSE, 6 1/4"	SO YD	2348	2348				
35600708	HOT-MIX ASPHALT BASE COURSE WIDENING, 8"	SO YD	926	926				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	22	22				
40600300	AGGREGATE (PRIME COAT)	TON	46	46				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5	5				
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	372	372				
40600895	CONSTRUCTING TEST STRIP	EACH	3	3				

* SPECIALTY ITEMS
 Δ NON PARTICIPATING ITEMS
 + NORTH AURORA FIRE PROTECTION DISTRICT

COMPANY NAME: HRGreen
 PROJECT CONTACT: HRGreen.com
 CLIENT: HRGreen.com
 DATE PLOTTED: 7/5/2012 1:28:16 PM
 PLOT SCALE: N/A
 PLOT DATE: 7/5/2012
 PLOT USER: T. HAMILTON
 PLOT TABLE:

 HRGreen.com <small>McGraw-Hill Construction Information Group</small>	USER NAME: cbr-the DESIGNED: C. HARTKE DRAWN: S. PERNAL CHECKED: T. HAMILTON PLOT DATE: 7/5/2012	REVISED: - REVISED: - REVISED: - REVISED: -
--	--	--

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES ILLINOIS ROUTE 31 AT MOOSEHEART ROAD	
SCALE: N/A	SHEET NO. 2 OF 12 SHEETS
STA.	TO STA.

F.A. RTE. 3887	SECTION AR-N-2	COUNTY KANE	TOTAL SHEETS 85	SHEET NO. 5
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
CONTRACT NO. 60P65				