

STP(M)

CMAQ(CMM)

STP(M)

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FED	80% FED	80% FED	80% FED	100% FPD +
				20% STATE	13.4% STATE	20% STATE	20% STATE	EVP
				ROADWAY	SIGNALS	INTERCONNECT	RET WALL	
				0004	0021	0021	0040	0021
				URBAN	URBAN	URBAN	URBAN	URBAN
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	60	60				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	246	246				
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	590	590				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	79	79				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1303	1303				
42001300	PROTECTIVE COAT	SO YD	838	838				
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	140	140				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	80	80				
44000100	PAVEMENT REMOVAL	SO YD	130	130				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	5620	5620				
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	935	935				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2170	2170				
44002248	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 12"	SO YD	420	420				
44201725	CLASS D PATCHES, TYPE I, 7 INCH	SO YD	10	10				
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SO YD	30	30				

- SPECIALTY ITEMS
- △ NON PARTICIPATING ITEMS
- + NORTH AURORA FIRE PROTECTION DISTRICT

COMPANY NAME: HRGreen
 PROJECT CONTACT: HRGreen.com
 CLIENT: HRGreen.com
 DATE PLOTTED: 7/5/2012 12:01:19 PM
 FILE NAME: 86100195.rvt
 PLOT DRIVER: pldrvr
 PEN TABLE: s:\table\dr\table.tbl



USER NAME: c:\hrtk	DESIGNED - C. HARTKE	REVISED -
PLOT SCALE: N/A	DRAWN - S. PERNAL	REVISED -
PLOT DATE: 7/5/2012	CHECKED - T. HAMILTON	REVISED -
	DATE - 7/5/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
ILLINOIS ROUTE 31 AT MOOSEHEART ROAD

SCALE: N/A SHEET NO. 3 OF 12 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3887	AR-N-2	KANE	85	6
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 60P65	