


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	STP (M)	CMAQ (CMM)			STP (M)
				CONSTRUCTION CODE				
				80% FED 20% STATE ROADWAY 0004 URBAN	80% FED 13.4% STATE 6.6% COUNTY SIGNALS 0021 URBAN	80% FED 20% STATE INTERCONNECT 0021 URBAN	80% FED 20% STATE RET WALL 0040 URBAN	100% FPD + EVP 0021 URBAN
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	21,650				21,650	
50901750	PARAPET RAILING	FOOT	375				375	
51500100	NAME PLATES	EACH	1				1	
54200217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	206	206				
54200223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	51	51				
54200229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	78	78				
54010302	PRECAST CONCRETE BOX CULVERTS 3' X 2'	FOOT	50	50				
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1				
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1				
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	1				
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	220	220				
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	456	456				
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	144	144				
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	41	41				
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	126	126				

- SPECIALTY ITEMS
- △ NON PARTICIPATING ITEMS
- + NORTH AURORA FIRE PROTECTION DISTRICT *Rex*

COMPANY NAME: HRGreen
 PROJECT CONTACT: HRGreen.com
 CLIENT: HRGreen.com
 DATE PLOTTED: 7/5/2012 12:29 PM
 FILE NAME: 86001961.dwg
 PLOT DEVICE: plot24
 PLOT TABLE:



USER NAME: charthe	DESIGNED - C. HARTKE	REVISED -
PLLOT SCALE: N/A	DRAWN - S. PERNAL	REVISED -
PLLOT DATE: 7/5/2012	CHECKED - T. HAMILTON	REVISED -
	DATE - 7/5/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES		
ILLINOIS ROUTE 31 AT MOOSEHEART ROAD		
SCALE: N/A	SHEET NO. 5 OF 12 SHEETS	STA. TO STA.

F.A. RTE. 3887	SECTION AR-N-2	COUNTY KANE	TOTAL SHEETS 85	SHEET NO. 8
FED. ROAD DIST. NO. ILLINOIS			FED. AID PROJECT CONTRACT NO. 60P65	