

STP (M)

CMAQ (CMM)

STP (M)

CONSTRUCTION CODE

80% FED 20% STATE ROADWAY	80% FED 13.4% STATE 6.6% COUNTY SIGNALS	80% FED 20% STATE INTERCONNECT	80% FED 20% STATE RET WALL	100% FPD + EVP
0004	0021	0021	0040	0021
URBAN	URBAN	URBAN	URBAN	URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FED 20% STATE ROADWAY	80% FED 13.4% STATE 6.6% COUNTY SIGNALS	80% FED 20% STATE INTERCONNECT	80% FED 20% STATE RET WALL	100% FPD + EVP
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10				
67100100	MOBILIZATION	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4300	4300				
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	260	260				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	28275	28275				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	470	470				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	198	198				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	24	24				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1435	1435				
* 72000100	SIGN PANEL - TYPE 1	SO FT	69.5	62	7.5			
* 72000200	SIGN PANEL - TYPE 2	SO FT	42	21	21			
* 72900200	METAL POST - TYPE B	FOOT	105	105				
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	75	75				
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6075	6075				
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	540	540				

- SPECIALTY ITEMS
- △ NON PARTICIPATING ITEMS
- + NORTH AURORA FIRE PROTECTION DISTRICT

COMPANY NAME: HRGreen
 PROJECT CONTACT: HRGreen
 DATE PLOTTED: 7/5/2012 10:23:35 AM
 FILE NAME: B6100106_14-sum-01.dgn
 PLOT DRIVER: pdfLsp
 PER TABLE: standard-trans.tbl

HRGreen.com Professional Design Firm # 154-001332	DESIGNED - C. HARTKE DRAWN - S. PERNAL CHECKED - T. HAMILTON DATE - 7/5/12	REVISED - REVISED - REVISED - REVISED -
---	---	--

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES	
ILLINOIS ROUTE 31 AT MOOSEHEART ROAD	
SCALE: N/A	SHEET NO. 7 OF 12 SHEETS STA. TO STA.

F.A. RTE. 3987	SECTION AR-N-2	COUNTY KANE	TOTAL SHEETS 85	SHEET NO. 10
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60P65	