

STP (M)

CMAQ (CMM)

STP (M)

CONSTRUCTION CODE

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | 80% FED 20% STATE ROADWAY | 80% FED 13.4% STATE 6.6% COUNTY SIGNALS | 80% FED 20% STATE INTERCONNECT | 80% FED 20% STATE RET WALL | 100% FPD + EVP |
|--------------|-------------------------------------------------------|------|----------------|---------------------------------|--------------------------------------------------|--------------------------------------|----------------------------------|-------------------|
| | | | | 0004 URBAN | 0021 URBAN | 0021 URBAN | 0040 URBAN | 0021 URBAN |
| • 87800100 | CONCRETE FOUNDATION, TYPE A | FOOT | 20 | | 20 | | | |
| • 87800150 | CONCRETE FOUNDATION, TYPE C | FOOT | 4 | | 4 | | | |
| • 87800415 | CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER | FOOT | 26 | | 26 | | | |
| • 87900200 | DRILL EXISTING HANDHOLE | EACH | 1 | | | 1 | | |
| • 88030020 | SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED | EACH | 4 | | 4 | | | |
| • 88030050 | SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED | EACH | 2 | | 2 | | | |
| • 88030100 | SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED | EACH | 2 | | 2 | | | |
| • 88030110 | SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED | EACH | 2 | | 2 | | | |
| • 88030210 | SIGNAL HEAD, LED, 2-FACE, 3 SECTION, BRACKET MOUNTED | EACH | 1 | | 1 | | | |
| • 88030220 | SIGNAL HEAD, LED, 2-FACE, 5 SECTION, BRACKET MOUNTED | EACH | 1 | | 1 | | | |
| • 88500100 | INDUCTIVE LOOP DETECTOR | EACH | 6 | | 6 | | | |
| • 88600100 | DETECTOR LOOP, TYPE 1 | FOOT | 539 | | 539 | | | |
| Δ • 88700200 | LIGHT DETECTOR | EACH | 3 | | | | | 3 |
| Δ • 88700300 | LIGHT DETECTOR AMPLIFIER | EACH | 1 | | | | | 1 |
| X2130010 | EXPLORATION TRENCH, SPECIAL | FOOT | 100 | 100 | | | | |

- SPECIALTY ITEMS
- Δ NON PARTICIPATING ITEMS
- + NORTH AURORA FIRE PROTECTION DISTRICT

Rev.

COMPANY NAME: HRGreen
 PROJECT CONTACT: HRGreen.com
 CLIENT: HRGreen.com
 DATE PLOTTED: 7/5/2012 1:22:45 PM
 PLOT ENGINE: HRGreen.com
 PLOT TABLE: Standard-Trans.DWG



| | | |
|---------------------|----------------------|------------|
| USER NAME: char-the | DESIGNED: C. HARTKE | REVISED: - |
| PLOT SCALE: N/A | DRAWN: S. PERNAL | REVISED: - |
| PLOT DATE: 7/5/2012 | CHECKED: T. HAMILTON | REVISED: - |
| | DATE: 7/5/12 | REVISED: - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

| | |
|--------------------------------------|---------------------------|
| SUMMARY OF QUANTITIES | |
| ILLINOIS ROUTE 31 AT MOOSEHEART ROAD | |
| SCALE: N/A | SHEET NO. 10 OF 12 SHEETS |
| STA. TO STA. | |

| | | | | |
|---------------------|----------------|---------------------------|-----------------|--------------|
| F.A. RTE. 3887 | SECTION AR-N-2 | COUNTY KANE | TOTAL SHEETS 85 | SHEET NO. 13 |
| FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |
| CONTRACT NO. 60P65 | | | | |