

STP (M)

CMAQ (CMM)

STP (M)

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FED 20% STATE ROADWAY	80% FED 13.4% STATE 6.6% COUNTY SIGNALS	80% FED 20% STATE INTERCONNECT	80% FED 20% STATE RET WALL	100% FPD + EVP
				0004 URBAN	0021 URBAN	0021 URBAN	0040 URBAN	0021 URBAN
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	77.1	77.1				
Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1			1		
Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	2355				2355	
Z0300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	261.4	261.4				
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1		1			
Z0076600	TRAINEES	HOUR	500	500				
* A2000220	TREE, ACER X FREEMANII MARMO (MARMO FREEMAN MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	10	10				
* A2001720	TREE, ACER SACCHARUM (SUGAR MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	10	10				
* A2005616	TREE, OSTRYA VIRGINIANA (AMERICAN HOP HORNBEAM), 2" CALIPER, BALLED AND BURLAPPED	EACH	3	3				
* A2006716	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	5	5				
* A2006816	TREE, QUERCUS MUEHLENBERGII (CHINKAPIN OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	6	6				
* K0029634	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	2	2				
* X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	4835.5	4835.5				

- \* SPECIALTY ITEMS
- △ NON PARTICIPATING ITEMS
- + NORTH AURORA FIRE PROTECTION DISTRICT

COMPANY NAME: HRGreen.com  
 PROJECT CONTACT: [blank]  
 CLIENT: [blank]  
 DATE PLOTTED: 7/5/2012 12:25:51 PM  
 PLOT SCALE: N/A  
 PLOT DATE: 7/5/2012



HRGreen.com  
 41544001322

USER NAME: charthe	DESIGNED - C. HARTKE	REVISED -
PLOT SCALE: N/A	DRAWN - S. PERNAL	REVISED -
PLOT DATE: 7/5/2012	CHECKED - T. HAMILTON	REVISED -
	DATE - 7/5/12	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES	
ILLINOIS ROUTE 31 AT MOOSEHEART ROAD	
SCALE: N/A	SHEET NO. 12 OF 12 SHEETS
STA. [blank]	TO STA. [blank]

F.A. RTE. 3887	SECTION AR-N-2	COUNTY KANE	TOTAL SHEETS 85	SHEET NO. 15
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60P65	