



NOTES:

1. USE BLACK LETTERING ON ORANGE BACKGROUND.
2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
3. ERECT SIGN ① WITH INSTALLED PANEL ② ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
4. REMOVE PANEL ② SOON AFTER THE START OF CONSTRUCTION.
5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

COMPANY NAME: HRGreen
 PROJECT CONTACT: HRGreen.com
 DATE PLOTTED: 6/26/2012 10:06:17 PM
 FILE NAME: 8610019614-09-12.dgn
 PLOT DRIVER: pdf.plt
 PEN TABLE: standard-trans.tbl

FILE NAME: HRGreen.com	USER NAME: geglentobt	DESIGNED: -	REVISED: - R. MIRS 09-15-97
DATE PLOTTED: 6/26/2012 10:06:17 PM		DRAWN: -	REVISED: - R. MIRS 12-11-97
FILE NAME: 8610019614-09-12.dgn		CHECKED: -	REVISED: - T. RAMMACHER 02-02-99
PLOT DRIVER: pdf.plt		DATE: -	REVISED: - C. JUCIUS 01-31-07
PEN TABLE: standard-trans.tbl			

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

ARTERIAL ROAD
 INFORMATION SIGN

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3887	AR-N-2	KANE	85	73
TC-22		CONTRACT NO. 60P65		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				