

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	TYPICAL SECTIONS
5	ALIGNMENT, TIES AND BENCHMARKS PLAN
6	SIGNING PLAN
7-8	EXISTING AND PROPOSED ROADWAY PLANS
9-10	EXISTING AND PROPOSED DRAINAGE PLANS
11	ARTERIAL ROAD INFORMATION SIGN (TC-22)
12	DRIVEWAY ENTRANCE SIGNING (TC-26)

STATE STANDARDS

STANDARD NO.	DESCRIPTION
602301 - 03	INLET - TYPE A
604006 - 04	FRAME AND GRATE TYPE 3
606001 - 04	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
630001 - 10	STEEL PLATE BEAM GUARDRAIL
630301 - 05	SHOULDER WIDENING FOR TYPE (SPECIAL) GUARDRAIL TERMINAL
635006 - 03	REFLECTOR AND TERMINAL MARKER PLACEMENT
664001 - 02	CHAIN LINK FENCE
701301 - 04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701501 - 06	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701901 - 02	TRAFFIC CONTROL DEVICES
720001 - 01	SIGN PANEL MOUNTING DETAILS

701101 - 02
 701601 - 07
 701602 - 05
 701606 - 08
 701701 - 08

GENERAL NOTES:

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. 48 HOUR NOTIFICATION IS REQUIRED.

TEN (10) FOOT TRANSITIONS SHALL BE USED TO MATCH PROPOSED CURB AND GUTTER AND MEDIAN ITEMS OF WORK TO EXISTING CURBS AND GUTTER AND MEDIANS IN THE FIELD, UNLESS OTHERWISE SHOWN. THE TRANSITIONS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PROPOSED ITEMS OF WORK SPECIFIED.

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE VILLAGES OF HODGKINS AND MCCOOK.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

THE REMOVAL OF GUARDRAIL TERMINAL SECTIONS SHALL BE INCLUDED IN THE UNIT PRICE PER FOOT FOR "GUARDRAIL REMOVAL."

ALL DAMAGE TO EXISTING PAVEMENT MARKINGS OR RAISED REFLECTIVE PAVEMENT MARKERS OUTSIDE THE REMOVAL LINE SHOWN ON THE PLANS SHALL BE REPLACED AT NO ADDITIONAL COST TO THE DEPARTMENT.

BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFLECTIVE PAVEMENT MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATIONS OF ALL PAVEMENT MARKINGS SHALL BE AS DIRECTED BY THE ENGINEER.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847)705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM THE BUREAUS OF MAINTENANCE AND CONSTRUCTION.

THE THICKNESS OF THE HMA MIXTURE SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HMA MIXTURE IS PLACED.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

FOR FRAMES AND LIDS ADJUSTMENT WITHOUT MILLING, REUSE EXISTING FRAME AND LID UNLESS OTHERWISE SPECIFIED IN THE PLANS.

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.

THE CONTRACTOR SHALL VERIFY THE EXISTING TYPE/HEIGHT OF EXISTING GUARDRAIL BEFORE ORDERING THE NEW TERMINAL SECTION. COST INCLUDED WITH THE COST OF THE TERMINAL. THE TERMINAL SECTION SHALL MATCH THE HEIGHT OF THE EXISTING GUARDRAIL.

THE CONTRACTOR SHALL SALVAGE AND RETURN THE EXISTING DETOUR SIGNS, TRAFFIC BARRICADES, GUARDRAIL, AND BARRIER WALLS TO:

SOUTH SIDE SIGN SHOP
 CONTACT: FRANK VITAGLIANO (708) 544-9372

THIS WORK SHALL INCLUDE REMOVING, TRANSPORTING, AND UNLOADING THE EXISTING SIGNS TO THE ABOVE YARD, WHICH COST IS INCLUDED IN THE COST OF "REMOVE EXISTING SIGN PANEL."

Rev. 10-25-12

FILE NAME =	USER NAME = windat	DESIGNED -	REVISED -	STATE OF ILLINOIS	JOLIET RD EAST OF LENZI AVE INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pwork\windat\0254803\PI359	shy-gennote.dgn	DRAWN -	REVISED -			3562	430Y-N	COOK	12	2	
	PLOT SCALE = 1/8" = 1' / in.	CHECKED -	REVISED -			SHEET OF SHEETS STA. TO STA.		CONTRACT NO. 60T48			
	PLOT DATE = 8/24/2012	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					