

INDEX OF SHEETS

1	TITLE SHEET
2	INDEX OF SHEETS, IDOT STANDARDS, AND GENERAL NOTES
3 - 4	SUMMARY OF QUANTITIES
5	TYPICAL SECTIONS
6	ALIGNMENT, TIES, AND BENCHMARKS
7	EXISTING AND REMOVAL PLAN
8	PLAN & PROFILE
9	MAINTENANCE OF TRAFFIC TYPICAL
10	MAINTENANCE OF TRAFFIC PLAN STAGE I
11	MAINTENANCE OF TRAFFIC PLAN STAGE II
12	GENERAL PLAN & ELEVATION
13	GENERAL NOTES, INDEX OF SHEETS AND TOTAL BILL OF MATERIAL
14	STAGE CONSTRUCTION
15	STAGE CONSTRUCTION DETAILS
16	REMOVAL DETAILS
17	17" x 36" PCC DECK BEAM DETAILS 1
18	17" x 36" PCC DECK BEAM DETAILS 2
19	TYPICAL CROSS SECTION
20	PARAPET, SIDEWALK AND MEDIAN DETAILS
21	ALUMINUM RAILING TYPE L
22	ABUTMENT ELEVATIONS
23	ABUTMENT SECTIONS
24	APPROACH SLAB DETAILS 1
25	APPROACH SLAB DETAILS 2
26	TOP OF APPROACH SLAB ELEVATIONS
27	TRENCH DRAIN DETAIL
28	URBAN LANE CLOSURE MULTILANE, TWO WAY, WITH MOUNTABLE MEDIAN
28	TRAFFIC CONTROL AND PROTECTION FOR SIDEROADS, INTERSECTIONS AND DRIVEWAYS
29	DIRECTION INDICATOR BARRICADES
30	WORK ZONE SPEED LIMIT SIGNING DIAGRAM
31 - 32	TYPICAL PAVEMENT MARKINGS FOR COUNTY HIGHWAYS
33	CONCRETE WASHOUT FACILITIES
34	DRAINAGE STRUCTURE RIM ELEVATIONS AND OFFSETS
35	TYPICAL APPLICATIONS RAISED REFLECTOR PAVEMENT MARKERS (SNOW PLOW RESISTANT)
36	BUTT JOINT AND HMA TAPER DETAILS
37	ARTERIAL ROAD INFORMATION SIGN

LIST OF STANDARDS

NUMBER	STATE STANDARD
000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
280001-06	TEMPORARY EROSION CONTROL SYSTEMS
420401-08	BRIDGE APPROACH PAVEMENT CONNECTOR
515001-03	NAME PLATES FOR BRIDGES
606001-04	CONCRETE CURB TYPE B AND COMBINATION CURB AND GUTTER
630001-10	STEEL PLATE BEAM GUARDRAIL
631011-08	TRAFFIC BARRIER TERMINAL, TYPE 2
631026-05	TRAFFIC BARRIER TERMINAL, TYPE 5
631031-10	TRAFFIC BARRIER TERMINAL, TYPE 6
635001-01	DELINEATORS
635006-03	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-02	REFLECTOR MARKER AND MOUNTING DETAILS
701101-02	OFF-ROAD OPERATIONS, MULTILANE, 15' (4.5M) TO 24' (600MM) FROM PAVEMENT EDGE
701801-05	LANE CLOSURE, MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
701901-02	TRAFFIC CONTROL DEVICES
704001-07	TEMPORARY CONCRETE BARRIER
780001-03	TYPICAL PAVEMENT MARKINGS
781001-03	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS

GENERAL NOTES

- ALL CONSTRUCTION SHALL BE IN CONFORMANCE WITH THE APPLICABLE REQUIREMENT SET FORTH IN "THE CONSTRUCTION SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED JANUARY 1, 2012 THEREINAFTER REFERRED TO AS STANDARD SPECIFICATIONS. THE LATEST EDITION OF THE "ILLINOIS MANUAL ON UNIFORM MANUAL TRAFFIC CONTROL DEVICES FOR STREETS & HIGHWAYS" IN EFFECT ON THE DATE OF INVITATION FOR BIDS; THE "SUPPLEMENTAL SPECIFICATIONS & RECURRING SPECIAL PROVISIONS" ADOPTED JANUARY 1, 2012; SPECIAL PROVISIONS AS INCLUDED IN THE CONTRACT DOCUMENTS; AND THE DETAILS AND STANDARDS CONTAIN IN THESE PLANS.
- BEFORE STARTING ANY EXCAVATIONS, THE CONTRACTOR SHALL CALL "JULIE" AT 1-800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE & GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED)
- THE LOCATIONS OF THE EXISTING UTILITIES, AS SHOWN ON THE DRAWINGS, REPRESENT DATA RECEIVED FROM VARIOUS SOURCES; IT IS NOT GUARANTEED TO BE CORRECT OR ALL INCLUSIVE. THE CONTRACTOR SHALL CONDUCT HIS OWN INVESTIGATIONS INTO THE LOCATION, SIZE, DEPTH, AND NATURE OF ANY AND ALL EXISTING UTILITIES WHICH MAY INTERFERE WITH THE WORK UNDER THIS CONTRACT. ANY EXISTING UTILITIES WHICH ARE TO REMAIN IN SERVICE SHALL BE FULLY PROTECTED BY THE CONTRACTOR AND ANY DAMAGE CAUSED BY THE CONSTRUCTION SHALL BE IMMEDIATELY REPAIRED AT THE CONTRACTOR'S EXPENSE.
- THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, LAKE COUNTY DIVISION OF TRANSPORTATION, THE VILLAGE OF BUFFALO GROVE, AND THE LAKE COUNTY FOREST PRESERVE DISTRICT.
- ALL WORK SHALL BE COMPLETED WITHIN THE LIMITS OF THE PROJECT SHOWN. NO EQUIPMENT, MATERIALS OR A YARD OR FIELD OFFICE SHALL BE SET UP OR STORED ON COUNTY OR PRIVATE PROPERTY WITHOUT WRITTEN PERMISSION OF THE COUNTY OR THE PROPERTY OWNER.
- ALL EXCAVATION AND EMBANKMENT LOCATIONS REQUIRING SEEDING OR SODDING SHALL BE CONSTRUCTED TO 4 IN BELOW FINISHED GRADE LINE TO ALLOW TOPSOIL PLACEMENT.
- PAVEMENT ELEVATIONS: THE ELEVATIONS SHOWN ON THE PLANS ARE FINISHED GRADES FOR THE PAVEMENT OR SURFACE COURSE, UNLESS OTHERWISE INDICATED.
- PROTECTION OF AND RESTORATION OF TRAFFIC SIGNS: PRIOR TO THE BEGINNING OF CONSTRUCTION OPERATIONS, THE CONTRACTOR WILL PROVIDE A SIGN LOG OF ALL EXISTING SIGNS WITHIN THE LIMITS OF THE CONSTRUCTION ZONE. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING THE ACCURACY OF THE SIGN LOG THROUGHOUT THE DURATION OF THIS PROJECT. THIS WORK IS CONSIDERED INCLUDED IN THE COST OF THE CONTRACT. ALL EXISTING TRAFFIC SIGNS SHALL MAINTAIN, FURNISH, AND REPLACE AT HIS EXPENSE, ANY TRAFFIC SIGN OR POST WHICH HAS BEEN DAMAGED OR LOST BY THE CONTRACTOR.
- TRAFFIC CONTROL DEVICES: ALL TRAFFIC CONTROL DEVICES USED FOR THE MAINTENANCE OF TRAFFIC AS DETAILED ON THE PLANS SHALL BE REFLECTORIZED PRIOR TO INSTALLATION AND CLEANED AS NECESSARY THROUGHOUT THE DURATION OF THE CONTRACT.

10. DURING CONSTRUCTION OPERATIONS ANY CONSTRUCTION DEBRIS DEPOSITED IN THE FLOW LINE DRAINAGE STRUCTURE SHALL BE REMOVED AT THE CLOSE OF EACH WORKING DAY AT THE CONCLUSION OF THE CONSTRUCTION OPERATIONS. ALL DRAINAGE STRUCTURES SHALL BE CLEANED AS NECESSARY TO INSURE THAT THEY ARE FREE FROM ALL DIRT AND CONSTRUCTION DEBRIS PRIOR TO THE FINAL INSPECTION OF THE PROJECT. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCLUDED IN THE COST OF EARTH EXCAVATION.

- RIM ELEVATION AND OFFSET OF DRAINAGE STRUCTURES ARE MEASURED TO EDGE OF PAVEMENT.
- THE WORK OUTSIDE THE LIMITS OF BRIDGE APPROACH PAVEMENT, ALL REFERENCES IN THE HIGHWAY STANDARDS AND STANDARD SPECIFICATIONS FOR REINFORCEMENT, DOWEL BARS AND TIE BARS IN PAVEMENT, SHOULDERS, CURBS, COMBINATION CURB AND GUTTER AND MEDIAN, AND CHAIR SUPPORTS FOR "CRC" PAVEMENT, SHALL BE EPOXY COATED, UNLESS NOTED ON THE PLAN.

13. UTILITIES CONTACTS:
- | | | |
|--|---|---|
| J.U.L.I.E.
JOINT UTILITY LOCATION FOR EXCAVATORS
(800) 892-0123 OR 811 | LAKE COUNTY DEPT OF PUBLIC WORKS
688 INDUSTRIAL DRIVE
ELMHURST, IL 60126
GORDON WHITE
(847) 377-7135 | COMCAST
688 INDUSTRIAL DRIVE
ELMHURST, IL 60126
(630) 600-6352
ROBERT SCHULTER JR
BOB_SCHULTER@CABLE.COMCAST.COM |
| ILLINOIS DEPARTMENT OF TRANSPORTATION
201 WEST CENTER COURT
SCHAUMBURG, IL 60196
GEORGE GUDERLEY
AREA PERMIT COORDINATOR
(847) 705-4131 | LAKE COUNTY DIVISION OF TRANSPORTATION
600 W. WINCHESTER RD
LIBERTYVILLE, IL 60048
JON NELSON
ENGINEER OF TRAFFIC
(847) 377-7400 | VILLAGE OF BUFFALO GROVE
51 RAUPP BOULEVARD
BUFFALO GROVE, IL 60089
(847) 459-2547
GREG BOYSEN |
| NICOR GAS
1844 FERRY ROAD
NAPERVILLE, IL 60563
CONSTANCE LANCE
(630) 388-3830
CLANE@NICOR.COM | COMED
1500 FRANKLIN BOULEVARD
LIBERTYVILLE, IL 60048
ATTENTION: TERRI BLECK
(847) 816-5239
TERRI.BLECK@COMED.COM | AT&T
1000 COMMERCE DRIVE,
FLOOR 2
OAKBROOK, IL 60523
BRUCE BROWN
(630) 573-5715
BB2439@ATT.COM |
| LAKE COUNTY FOREST PRESERVE DISTRICT
1899 WEST WINCHESTER ROAD
LIBERTYVILLE, IL 60046
JOHN NELSON
DISTRICT ENGINEER
(847) 968-3407 | | |

NOTE: "THE ILLINOIS DEPARTMENT OF TRANSPORTATION IS NOT THE OWNER OF RECORD FOR THIS BRIDGE. THOSE SEEKING HISTORIC, AS-BUILT OR OTHER EXISTING DOCUMENTS AND OWNER OF RECORD PLANS MUST CONTACT THE COUNTY TO MAKE ARRANGEMENTS FOR ACCESS TO THIS INFORMATION."

FILE NAME = L01143-shr-gennote.dgn	USER NAME = 3282111143	DESIGNED - TC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, IDOT STANDARDS, AND GENERAL NOTES		F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1:8000' / in.	DRAWN - LOM	REVISED -				2626	10-00193-07-0R	LAKE	37	2
	PLOT DATE = 8/28/2012	CHECKED - PK	REVISED -		SCALE: NTS	SHEET 1 OF 1 SHEETS	STA. N/A	TO STA. N/A	ILLINOIS FED. AID PROJECT CONTRACT NO. 63713		
		DATE - 4/2012	REVISED -								