

SUMMARY OF QUANTITIES

SPECIALITY ITEMS	SPECIAL PROVISIONS	CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0014	CONSTRUCTION TYPE CODE 0042	NON-PARTICIPATING
		20200100	EARTH EXCAVATION	CU YD	67	67		
		20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	34	34		
		20400800	FURNISHED EXCAVATION	CU YD	50	50		
		21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	592	592		
		25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25		
		25000400	NITROGEN FERTILIZER NUTRIENT	POUND	11	11		
		25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	11	11		
		25100630	EROSION CONTROL BLANKET	SQ YD	592	592		
		28000500	INLET AND PIPE PROTECTION	EACH	3	3		
		35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	152	152		
		40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	41	41		
		40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	24	24		
		40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	88	88		
		42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	32	32		
		44000100	PAVEMENT REMOVAL	SQ YD	343	343		
		44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	701	701		
		44000600	SIDEWALK REMOVAL	SQ FT	258	258		
		50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1		
		50102400	CONCRETE REMOVAL	CU YD	14	14.2		
		50300225	CONCRETE STRUCTURES	CU YD	19	19.0		
		50300255	CONCRETE SUPERSTRUCTURE	CU YD	115	115		
		50300300	PROTECTIVE COAT	SQ YD	268	268		
		50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	1,606	1,606		
		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	26,380	26,380		
S		50900105	ALUMINUM RAILING, TYPE L	FOOT	86	86		
		51500100	NAME PLATE	EACH	1	1		

SUMMARY OF QUANTITIES

SPECIALITY ITEMS	SPECIAL PROVISIONS	CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0014	CONSTRUCTION TYPE CODE 0042	NON-PARTICIPATING
		59000200	EPOXY CRACK INJECTION	FOOT	65	65		
		60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	1	1		
		60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	379	379		
		60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	62	62		
		60608521	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.24	FOOT	141	141		
S		63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1		
S		63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1	1		
S		63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1		
S		63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1		
		63200310	GUARDRAIL REMOVAL	FOOT	183	183		
S		63500105	DELINEATORS	EACH	1	1		
S		63500310	REMOVE AND REINSTALL DELINEATOR	EACH	1	1		
		67100100	MOBILIZATION	L SUM	1	1		
		70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	21	21		
		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2,131	2,131		
		70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	1,567	1,567		
		70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	404	404		
		70400100	TEMPORARY CONCRETE BARRIER	FOOT	575	575		
		70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	438	438		
		72400310	REMOVE SIGN PANEL - TYPE I	SQ FT	48	48		
		72400710	RELOCATE SIGN PANEL - TYPE I	SQ FT	48	48		
S		78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	225	225		
S		78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	180	180		
S		78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	403	403		
S		78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	322	322		
S		78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	12	12		

FILE NAME = LC1143-shr-500.dgn

USER NAME = 328211143

DESIGNED - TC

REVISED -

DRAWN - LOM

REVISED -

CHECKED - PK

REVISED -

DATE - 4/2012

REVISED -

PLOT SCALE = 50.0000' / in.

PLOT DATE = 8/28/2012

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NTS SHEET 1 OF 2 SHEETS STA. N/A TO STA. N/A

F.A.U. RTE. 2626

SECTION 10-00193-07-BR

COUNTY LAKE

TOTAL SHEETS 37

SHEET NO. 3

CONTRACT NO. 63713

ILLINOIS FED. AID PROJECT