

## INDEX OF SHEETS

SHEET NO.	DRAWING NO.	DESCRIPTION
1	CV-1	COVER SHEET
2	IS-1	INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES AND COMMITMENTS
3-7	SO-1 to SO-5	SUMMARY OF QUANTITIES
8	TYP-1	TYPICAL SECTIONS AND SCHEDULES
9	AT-1	ALIGNMENTS, TIES, AND BENCHMARKS
10	PP-1	EXISTING AND PROPOSED PLAN AND PROFILE
11	MOT-1	MAINTENANCE OF TRAFFIC GENERAL NOTES AND TYPICAL SECTIONS
12	MOT-2	MAINTENANCE OF TRAFFIC STAGE I AND STAGE II
13	EC-1	EROSION AND SEDIMENT CONTROL GENERAL NOTES, STRATEGY AND PLAN
13A	EC-1A	EROSION AND SEDIMENT CONTROL DETAILS
14		GENERAL PLAN AND ELEVATION
15		STAGED CONSTRUCTION AND DRAINAGE DETAILS
16		TEMPORARY CONCRETE BARRIER
17		SUPERSTRUCTURE
18		SUPERSTRUCTURE DETAILS
19		27"X36" PPC DECK BEAM
20		27"X36" PPC DECK BEAM DETAILS
21		27"X48" PPC DECK BEAM
22		27"X48" PPC DECK BEAM DETAILS
23-24		TIMBER RAILING
25		ABUTMENTS
26		BAR SPLICER ASSEMBLY DETAILS
27		METAL SHELL PILE DETAILS
28-29		SOIL BORING LOGS
30	BD-51	DISTRICT 1 DETAIL - BENCHING DETAIL FOR EMBANKMENT WIDENING
31-36	XS-PRE-1 to XS-PRE-6	WOODLAND DRIVE PRE-STAGE CROSS SECTIONS
37-41	XS-1 to XS-5	WOODLAND DRIVE CROSS SECTIONS

## HIGHWAY STANDARDS

STANDARD NO.	TITLE
000001-06	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
202001-01	EARTH MEDIAN DITCH CHECK
280001-06	TEMPORARY EROSION CONTROL SYSTEMS
420001-07	PAVEMENT JOINTS
515001-03	NAME PLATE FOR BRIDGES
601101-01	CONCRETE HEADWALL FOR PIPE DRAINS
635006-03	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-02	REFLECTOR MARKER AND MOUNTING DETAILS
701301-04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701321-12	LANE CLOSURE, 2L, 2W BRIDGE REPAIR WITH BARRIER
701901-02	TRAFFIC CONTROL DEVICES
704001-07	TEMPORARY CONCRETE BARRIER
BLR 14-10	PORTLAND CEMENT CONCRETE PAVEMENT (NONREINFORCED)
BLR 23-4	TRAFFIC BARRIER TERMINAL TYPE 1
BLR 26-3	STEEL PLATE BEAM GUARDRAIL 29" (731mm) HEIGHT
BLR 27-1	TRAFFIC BARRIER TERMINAL 5A

## GENERAL NOTES

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL J.U.L.I.E. AT (800) 892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. 48 HOUR NOTIFICATION IS REQUIRED.
- MEMBERS OF JULIE KNOWN TO BE WITHIN THE LIMITS OF THE IMPROVEMENT ARE: COMED, NICOR GAS, COMCAST AND AT&T.
- ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.
- THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, VILLAGE OF LAKE BARRINGTON, AND LAKE COUNTY.
- DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.
- IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS
- THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.
- THE LOCATIONS OF EXISTING DRAINAGE STRUCTURES, STORM SEWER, WATER MAIN, SANITARY SEWER, AND OTHER PUBLIC OR PRIVATE UTILITIES AS SHOWN ON THE PLANS IS APPROXIMATE, AND THEIR EXACT LOCATION IS TO BE DETERMINED IN THE FIELD BY THE CONTRACTOR. THIS WORK SHALL BE PER ARTICLES 105.07 AND 107.31 OF THE STANDARD SPECIFICATIONS. WHEN REQUIRED, LOCATING UTILITIES SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER FOOT FOR EXPLORATION TRENCH, SPECIAL.
- ABANDONED UNDERGROUND UTILITIES THAT CONFLICT WITH CONSTRUCTION SHALL BE DISPOSED OF OUTSIDE THE LIMITS OF THE RIGHT OF WAY ACCORDING TO ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS AND AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE COST OF EARTH EXCAVATION.
- SAWING OF REMOVAL ITEMS AS NOTED ON THE PLANS, SPECIFIED IN THE STANDARD SPECIFICATIONS, OR AS REQUIRED BY THE ENGINEER SHALL BE INCLUDED IN THE COST OF THE ITEM BEING REMOVED.
- ONLY THOSE TREES DESIGNATED BY THE ENGINEER, LISTED IN THE TREE REMOVAL SCHEDULE, OR SHOWN IN THE PLANS SHALL BE REMOVED. THE CONTRACTOR SHALL PROTECT ALL REMAINING TREES FROM DAMAGE DUE TO HIS OPERATIONS.
- ALL DAMAGE TO EXISTING PAVEMENT MARKINGS OR RAISED REFLECTIVE PAVEMENT MARKERS OUTSIDE THE REMOVAL LIMITS SHOWN ON THE PLANS SHALL BE REPLACED AT NO ADDITIONAL COST TO THE DEPARTMENT.

## COMMITMENTS

- (NONE)

FILE NAME = 10030-SHT-INDEX-GENNOTE.dgn	USER NAME = jehrhart	DESIGNED - MJT	REVISED 1 9/20/2012 J.C.E.	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES AND COMMITMENTS</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 1/8"=1'	CHECKED - E.J.G.	REVISED -	09-00010-00-BR			LAKE	41	2		
PLOT DATE = 05/14/12	DATE - 05/14/12	REVISED -	<b>IS-1</b>			CONTRACT NO. 63716		ILLINOIS FED. AID PROJECT		
				SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.			