

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				HBP FUNDING	
				80% FED 20% LAKE BARRINGTON ROADWAY	80% FED 20% LAKE BARRINGTON BRIDGE SN 049-6751
				0011 URBAN	0011 URBAN
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	66	66	
20200100	EARTH EXCAVATION	CU YD	12	12	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	87	87	
20300100	CHANNEL EXCAVATION	CU YD	296		296
20400800	FURNISHED EXCAVATION	CU YD	148	148	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	680	680	
25000312	SEEDING, CLASS 4A	ACRE	0.20	0.20	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18	18	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18	18	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18	18	
25100115	MULCH, METHOD 2	ACRE	0.4	0.4	
25100630	EROSION CONTROL BLANKET	SO YD	670	670	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	40	40	
28000305	TEMPORARY DITCH CHECKS	FOOT	56	56	

• DENOTES SPECIALTY ITEM