

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				HBP FUNDING	
				80% FED 20% LAKE BARRINGTON ROADWAY 0011 URBAN	80% FED 20% LAKE BARRINGTON BRIDGE SN 049-6751 0011 URBAN
28000400	PERIMETER EROSION BARRIER	FOOT	464	464	
28100107	STONE RIPRAP, CLASS A4	SQ YD	398		398
28200200	FILTER FABRIC	SQ YD	440		440
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	80	80	
42000201	PORTLAND CEMENT CONCRETE PAVEMENT 7" (JOINTED)	SQ YD	78	78	
42001300	PROTECTIVE COAT	SQ YD	78	78	
44000100	PAVEMENT REMOVAL	SQ YD	274	274	
48101498	AGGREGATE SHOULDERS, TYPE B 4"	SQ YD	198	198	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
50102400	CONCRETE REMOVAL	CU YD	111		111
50200100	STRUCTURE EXCAVATION	CU YD	213		213
50300225	CONCRETE STRUCTURES	CU YD	30.3		30.3
50300260	BRIDGE DECK GROOVING	SQ YD	185		185
50300280	CONCRETE ENCASEMENT	CU YD	6.6		6.6

• DENOTES SPECIALTY ITEM

FILE NAME = 10030-SHT-50002.dgn

USER NAME = jah-hart
 PLOT SCALE = 1/1
 PLOT DATE = 05/14/12

DESIGNED -
 DRAWN -
 CHECKED -
 DATE - 05/14/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 2 OF 5 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	09-00010-00-BR	LAKE	41	4
	SQ-2	CONTRACT NO. 63716		
ILLINOIS FED. AID PROJECT				