

# SCHEDULE OF QUANTITIES

TON	LOCATION	AREA (SQ YD)	DEPTH (IN)	QUANTITY
<b>40603310 HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50</b>				
	IL 84			
	STA. 941+39.93 TO 941+51.14 RT	6.9	2.00	0.77
	STA. 941+51.14 TO 942+01.00 RT	60.9	2.00	6.83
	STA. 942+01.00 TO 944+57.80 RT	199.7	2.00	22.37
	STA. 944+57.80 TO 944+83.80 RT	20.2	2.00	2.26
	STA. 944+83.80 TO 946+39.00 RT	120.7	2.00	13.52
	STA. 946+39.00 TO 946+49.25 RT	13.1	2.00	1.46
	STA. 946+49.25 TO 946+94.25 RT	39.1	2.00	4.38
	STA. 944+40.00 TO 945+00.00 RT/LT	173.33	2.00	19.41
	STA. 942+47.00 TO 942+58.80 LT	7.54	2.00	0.84
	STA. 942+58.80 TO 943+14.00 LT	69.00	2.00	7.73
	STA. 943+14.00 TO 944+57.80 LT	111.84	2.00	12.53
	STA. 944+57.80 TO 944+83.80 LT	20.22	2.00	2.26
	STA. 944+83.80 TO 947+77.00 LT	228.04	2.00	25.54
	STA. 947+77.00 TO 947+94.25 LT	21.08	2.00	2.36
	STA. 947+94.25 TO 948+36.50 LT	35.09	2.00	3.93
<b>TOTAL:</b>				<b>127.00 TON</b>

TON	LOCATION	AREA (SQ)	DEPTH (IN)	QUANTITY
<b>40800050 INCIDENTAL HOT-MIX ASPHALT SURFACING</b>				
	IL 84			
	STA. 942+58.80 TO 942+97.41	41.10	2.00	4.60
<b>TOTAL:</b>				<b>5.00 TON</b>

SO YD	LOCATION	AVE WIDTH (YD)	QUANTITY
<b>44201383 CLASS C PATCHES, TYPE IV, 12 INCH</b>			
	IL 84		
	STA. 944+40.00 TO 945+00.00	8.67	173.33
<b>TOTAL:</b>			<b>174.00 SO YD</b>

SO YD	LOCATION	QUANTITY
<b>48203021 HOT-MIX ASPHALT SHOULDERS, 6"</b>		
	IL 84	
	STA. 941+39.93 TO 944+57.80 RT	358.51
	STA. 944+57.80 TO 944+83.80 RT	22.39
	STA. 944+83.80 TO 946+94.25 RT	228.09
	STA. 942+47.00 TO 944+57.80 LT	242.88
	STA. 944+57.80 TO 944+83.80 LT	22.39
	STA. 944+83.80 TO 948+36.50 LT	387.20
<b>TOTAL:</b>		<b>1262.00 SO YD</b>

EACH	LOCATION	OFFSET (FT)	QUANTITY
<b>54215553 METAL END SECTIONS 18"</b>			
	IL 84		
	STA. 941+48.80	31.49 RT	1
	STA. 942+55.12	27.49 LT	1
	STA. 941+95.18	31.35 RT	1
	STA. 943+01.30	27.48 LT	1
<b>TOTAL:</b>			<b>4.00 EACH</b>

FOOT	LOCATION	QUANTITY
<b>52400223 PIPE CULVERTS, CLASS D, TYPE 1 18"</b>		
	IL 84	
	STA. 941+48.80 941+95.18 RT	46.38
	STA. 942+55.12 943+01.30 LT	46.18
<b>TOTAL:</b>		<b>93.00 FOOT</b>

EACH	LOCATION	OFFSET (FT)	QUANTITY
<b>60100060 CONCRETE HEADWALLS FOR PIPE DRAINS</b>			
	IL 84		
	STA. 944+40.00	32.50 RT	1.00
	STA. 944+40.00	29.00 LT	1.00
	STA. 945+00.00	28.50 RT	1.00
	STA. 945+00.00	32.00 LT	1.00
<b>TOTAL:</b>			<b>4.00 EACH</b>

FOOT	LOCATION	QUANTITY
<b>60107600 PIPE UNDERDRAINS 4"</b>		
	IL 84	
	STA. 944+40.00	70.00
	STA. 945+00.00	70.00
<b>TOTAL:</b>		<b>140.00 FOOT</b>

FOOT	LOCATION	QUANTITY
<b>63000001 STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS</b>		
	IL 84	
	STA. 943+64.25 TO 944+51.75 LT	87.50
	STA. 944+89.25 TO 947+14.25 LT	225.00
	STA. 942+51.75 TO 944+51.75 RT	200.00
	STA. 944+89.25 TO 945+89.25 RT	100.00
<b>TOTAL:</b>		<b>612.50 FOOT</b>

FOOT	LOCATION	QUANTITY
<b>63000025 STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES</b>		
	IL 84	
	STA. 944+51.75 TO 944+89.25 RT	37.50
	STA. 944+51.75 TO 944+89.25 LT	37.50
<b>TOTAL:</b>		<b>75.00 FOOT</b>

EACH	LOCATION	QUANTITY
<b>63100167 TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT</b>		
	IL 84	
	STA. 942+06.73	RT 1.00
	STA. 943+07.55	LT 1.00
	STA. 946+32.50	RT 1.00
	STA. 947+69.99	LT 1.00
<b>TOTAL:</b>		<b>4.00 EACH</b>

FOOT	LOCATION	QUANTITY
<b>63200310 GUARDRAIL REMOVAL</b>		
	IL 84	
	STA. 943+48.94 TO 943+74.34 RT	28.00
	STA. 943+74.34 TO 945+49.30 RT	174.96
	STA. 945+49.30 TO 945+74.48 RT	25.24
	STA. 943+42.45 TO 943+67.42 LT	25.01
	STA. 943+67.42 TO 945+41.92 LT	174.50
	STA. 945+41.92 TO 945+67.92 LT	26.06
<b>TOTAL:</b>		<b>454.00 FOOT</b>

EACH	LOCATION	QUANTITY
<b>63500105 DELINEATORS</b>		
	IL 84	
	STA. 942+00	RT 1.00
	STA. 943+00	LT 1.00
	STA. 947+80	RT 1.00
	STA. 947+80	LT 1.00
<b>TOTAL:</b>		<b>4.00 EACH</b>

FOOT	LOCATION	QUANTITY
<b>64200108 SHOULDER RUMBLE STRIPS, 8 IN</b>		
	IL 84	
	STA. 94247 TO 94837	LT 590
	STA. 94193 TO 94694	RT 501
<b>TOTAL:</b>		<b>1091.00</b>

EACH	LOCATION	QUANTITY
<b>66700305 PERMANENT SURVEY MARKERS, TYPE II</b>		
	IL 84	
	STA. 944+40.00 TO 945+00.00	2
<b>TOTAL:</b>		<b>2.00 EACH</b>

EACH	LOCATION	QUANTITY
<b>70106500 TEMPORARY BRIDGE TRAFFIC SIGNALS</b>		
	IL 84	
	PROJECT LIMITS	1
<b>TOTAL:</b>		<b>1.00 EACH</b>

EACH	LOCATION	QUANTITY
<b>70106700 TEMPORARY RUMBLE STRIPS</b>		
	IL 84	
	STAGE1/STAGE 2	6
<b>TOTAL:</b>		<b>6.00 EACH</b>

FILE NAME = S:\JUL16300-6399\6346\026\Micro\CAD\ Sheets\0264925\sh-t-schedule.dgn



1170 SOUTH HOUBOLT ROAD JOLIET, ILLINOIS 60431 (815) 744-4200	USER NAME = amanda.j	DESIGNED -	REVISED -
	PLOT SCALE = 40.0000' / in.	DRAWN -	REVISED -
	PLOT DATE = 8/15/2012	CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: AS SHOWN SHEET NO. 2 OF 3 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
308	110T	ROCK ISLAND	51	13
CONTRACT NO. 64925				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				