

SCHEDULE OF QUANTITIES

70300220 **TEMPORARY PAVEMENT MARKING - LINE 4"**

EQOI	LOCATION	QUANTITY
IL 84		
STAGE 1		
STA.	942+05.00 TO 948+62.00	658.80
STA.	943+02.30 TO 946+95.00	393.20
STAGE 2		
STA.	942+72.00 TO 946+53.50	382.50
STA.	940+00.00 TO 947+53.00	756.00
TOTAL:		2191.00 FOOT

78001110 **PAINT PAVEMENT MARKING - LINE 4"**

EQOI	LOCATION	QUANTITY
IL 84		
STA.	939+75.00 TO 949+13.00	12.00 LT 1876.00
STA.	939+75.00 TO 949+13.00	12.00 RT 1876.00
STA.	939+75.00 TO 949+13.00	2.00 LT 1876.00
STA.	939+75.00 TO 949+13.00	2.00 RT 1876.00
2 APPLICATIONS		
TOTAL:		7504.00 FOOT

Z0030250 **IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3**

EACH	LOCATION	QUANTITY
IL 84		
STA.	943+12.00	1
STA.	946+30.00	1
TOTAL:		2.00 EACH

70300280 **TEMPORARY PAVEMENT MARKING - LINE 24"**

EQOI	LOCATION	QUANTITY
IL 84		
STAGE 1 / STAGE 2		
STA.	938+90.00 TO 939+92.00	12.00
STA.	949+10.00 TO 949+12.00	12.00
TOTAL:		24.00 FOOT

78200410 **GUARDRAIL MARKERS, TYPE A**

EACH	LOCATION	LENGTH (FT)	QUANTITY
IL 84			
STA.	942+06.73 TO 946+32.50	425.77	6.00
STA.	943+07.55 TO 947+69.99	462.44	6.00
TOTAL:			12.00 EACH

Z0030350 **IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3**

EACH	LOCATION	QUANTITY
IL 84		
STA.	943+12.00	1
STA.	946+30.00	1
TOTAL:		2.00 EACH

70301000 **WORK ZONE PAVEMENT MARKING REMOVAL**

SO FT	LOCATION	OFFSET (FT)	OFFSET (FT)	LENGTH (FT)	WIDTH (IN)	QUANTITY
IL 84						
STAGE 1						
STA.	939+90.00	0.00	939+90.00	12.00	24.00	24.00
STA.	942+15.00	-13.00	943+15.00	1.00	100.98	33.66
STA.	943+15.00	1.00	943+81.00	6.50	66.23	22.08
STA.	943+81.00	6.50	946+28.00	6.50	247.00	82.33
STA.	946+28.00	6.50	948+52.00	-12.56	224.81	74.94
STA.	943+02.00	12.00	943+81.00	18.50	79.27	26.42
STA.	943+81.00	18.50	946+29.00	18.50	248.00	82.67
STA.	946+29.00	18.50	947+14.00	11.34	85.30	28.43
STAGE 2						
STA.	948+62.00	0.00	948+62.00	12.00	24.00	24.00
STA.	939+98.00	12.00	943+58.00	-8.00	360.56	120.19
STA.	943+58.00	-8.00	945+57.00	-8.00	199.00	66.33
STA.	945+57.00	-8.00	946+53.00	0.00	96.33	32.11
STA.	946+53.00	0.00	947+53.00	12.09	100.73	33.58
STA.	942+72.00	-13.00	943+60.00	-20.00	88.28	29.43
STA.	943+60.00	-20.00	945+57.00	-20.00	197.00	65.67
STA.	945+57.00	-20.00	946+53.00	-12.00	96.33	32.11
TOTAL:						778.00 SO FT

78201000 **TERMINAL MARKER - DIRECT APPLIED**

EACH	LOCATION	QUANTITY
IL 84		
STA.	942+06.73 TO RT	1
STA.	943+07.55 TO LT	1
STA.	946+32.50 TO RT	1
STA.	947+69.99 TO LT	1
TOTAL:		4.00 EACH

Z0062456 **TEMPORARY PAVEMENT**

SO YD	LOCATION	QUANTITY
IL 84		
STA.	943+00.00 7.12 946+95.00 7.65	324.12
TOTAL:		325.00 SO YD

78300100 **PAVEMENT MARKING REMOVAL**

SO FT	LOCATION	WIDTH (IN)	QUANTITY
IL 84			
STAGE 1			
STA.	942+15.00 TO 943+15.00	8.00	66.67
STA.	946+94.00 TO 948+62.00	8.00	112.00
STAGE 2			
STA.	939+90.00 TO 942+15.00	8.00	150.00
STA.	946+53.00 TO 948+62.00	8.00	139.33
TOTAL:			468.00 SO FT

70400100 **TEMPORARY CONCRETE BARRIER**

EQOI	LOCATION	QUANTITY
IL 84		
STAGE 1		
STA.	943+16.00 TO 944+15.00	99.35
STA.	944+15.00 TO 945+28.00	113.00
STA.	945+28.00 TO 946+27.00	99.36
TOTAL:		312.50 FOOT

X4400110 **TEMPORARY PAVEMENT REMOVAL**

SO YD	LOCATION	WIDTH (FT)	WIDTH (FT)	QUANTITY
IL 84				
STA.	943+00.00	7.12	946+95.00	7.65 324.12
TOTAL:				325.00 SO YD

70400200 **RELOCATE TEMPORARY CONCRETE BARRIER**

EQOI	LOCATION	QUANTITY
IL 84		
STAGE 2		
STA.	943+16.00 TO 944+15.00	99.63
STA.	944+16.00 TO 945+28.00	112.00
STA.	945+28.00 TO 946+28.00	100.36
TOTAL:		312.50 FOOT

Z0013798 **CONSTRUCTION LAYOUT**

L SUM	LOCATION	QUANTITY
IL 84		
STA.	939+75.00 TO 949+13.00	1.00
TOTAL:		1.00 L SUM

FILE NAME = S:\JOL\63800-63999\6346-026\Micros\CAD\ Sheets\0264925-sht-schedule.dgn