

CODE NUMBER	ITEM	UNIT	TOTAL	ROADWAY 0004	STRUCTURE NO. 038-2024 (PR) 038-0169 (EX) 0040
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	30	30	
20200100	EARTH EXCAVATION	CU YD	395	395	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	61		61
20400800	FURNISHED EXCAVATION	CU YD	730	730	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	408	408	
25000300	SEEDING, CLASS 3	ACRE	0.8	0.8	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	72	72	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	72	72	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	72	72	
25100630	EROSION CONTROL BLANKET	SQ YD	3,058	3,058	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	720	720	
28000305	TEMPORARY DITCH CHECKS	FOOT	94	94	
28000400	PERIMETER EROSION BARRIER	FOOT	156	156	
28000500	INLET AND PIPE PROTECTION	EACH	2	2	
28100107	STONE RIPRAP, CLASS A4	SQ YD	314		314
28200200	FILTER FABRIC	SQ YD	314		314
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	209	209	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	47	47	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	682	682	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	119	119	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	360	360	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	287	287	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	138	138	
44000100	PAVEMENT REMOVAL	SQ YD	162	162	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	149	149	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	482	482	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1

* SPECIALTY ITEM

CODE NUMBER	ITEM	UNIT	TOTAL	ROADWAY 0004	STRUCTURE NO. 038-2024 (PR) 038-0169 (EX) 0040
50105220	PIPE CULVERT REMOVAL	FOOT	64	64	
50800105	REINFORCEMENT BARS	POUND	10,390		10,390
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	700		700
51500100	NAME PLATES	EACH	1		1
54003000	CONCRETE BOX CULVERTS	CU YD	81.2		81.2
54011208	PRECAST CONCRETE BOX CULVERTS 12' x 8'	FOOT	84		84
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	168	168	
54213450	END SECTIONS 15"	EACH	4	4	
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	375	375	
63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	75	75	
63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	559	559	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	8	8	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2	
67100100	MOBILIZATION	L SUM	1	1	
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1	
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2,200	2,200	
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	280	280	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	8	8	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	8	8	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	8	8	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	8	8	
Z0054400	ROCK FILL	CU YD	57		57
X0322936	REMOVE EXISTING FLARED END SECTION	EACH	4	4	
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	150	150	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	

* SPECIALTY ITEM

FILE NAME =	USER NAME = #USER#	DESIGNED - JML	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN - JJO/DJM	REVISED -			840	138 BR-3	IROQUOIS	28	3	
		CHECKED - MSW	REVISED -			CONTRACT NO. 66971					
		DATE - 07-27-11	REVISED -			FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT					