

GUARDRAIL						
LOCATION	SPBGR TY A	TRAF BAR	TR BAR TRM	TR BAR TRM	GUARDRAIL	SPBGR
	6FT POSTS	TERM T6	T1 SPL TAN	T1 SPL FLR	REMOV	(SHORT RADIUS)
	FOOT	EACH	EACH	EACH	FOOT	FOOT
STA 859+98.21 RT TO STA 860+42.60 RT						62.5
STA 860+11.80 RT TO STA 861+75.99 RT					164	
STA 860+17.60 LT TO STA 860+67.60 LT				1		
STA 860+42.60 RT TO STA 861+17.60 RT	75					
STA 860+67.60 LT TO STA 861+17.60 LT	50					
STA 860+86.74 LT TO STA 861+76.11 LT					89	
STA 861+17.60 LT TO STA 861+61.35 LT		1				
STA 861+17.60 RT TO STA 861+61.35 RT		1				
STA 862+50.37 RT TO STA 863+41.59 RT					91	
STA 862+50.72 LT TO STA 864+40.79 LT					190	
STA 862+64.43 LT TO STA 863+08.18 LT		1				
STA 862+64.43 RT TO STA 863+08.18 RT		1				
STA 863+08.18 LT TO STA 864+58.18 LT	150					
STA 863+08.18 RT TO STA 863+58.18 RT	50					
STA 863+58.18 RT TO STA 864+08.18 RT				1		
STA 864+58.18 LT TO STA 865+08.43 LT				1		
N 300E ROAD, STA 30+54.50 LT TO STA 31+04.50 LT			1			
TOTAL	325	4	1	3	534	62.5

REFLECTORS / MARKERS				
LOCATION	RAISED REFL	GUARDRAIL	TERMINAL	RAISED REF
	PAVT MKR	MKR TYPE A	MARKER - DA	PVT MK REM
	EACH	EACH	EACH	EACH
STA 858+15.00 TO STA 866+20.00	11			11
STA 859+98.21 LT TO STA 861+61.35 RT		4		
STA 860+17.60 LT			1	
STA 860+17.60 LT TO STA 861+61.35 LT		4		
STA 862+64.43 LT TO STA 865+08.43 LT		4		
STA 862+64.43 RT TO STA 864+08.18 RT		4		
STA 864+08.18 RT			1	
STA 865+08.43 LT			1	
N 300E ROAD, STA 31+04.50 LT			1	
TOTAL	11	16	4	11

EPOXY PAVEMENT MARKING - LINE			
LOCATION	4"	6"	
	FOOT	FOOT	
STA 858+15.00 TO STA 866+20.00			210
STA 858+15.00 LT TO STA 859+25.00 LT	110		
STA 858+15.00 RT TO STA 859+25.00 RT	110		
STA 860+35.00 LT TO STA 866+20.00 LT	585		
STA 860+35.00 RT TO STA 866+20.00 RT	585		
TOTAL	1,390	210	

TRAFFIC CONTROL - ALL STAGES		
ITEM	UNIT	TOTAL
TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1
TRAFFIC CONTROL SURVEILLANCE	CAL DA	74
TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
SHORT TERM PAVEMENT MARKING	FOOT	252
TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5,223
TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	86
WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1,979
TEMPORARY CONCRETE BARRIER	FOOT	725
RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	700
IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2
IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2
IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2

RIGHT OF WAY MARKERS		
LOCATION	FUR ERECT	REMOVE
	ROW MARKERS	ROW MARKERS
	EACH	EACH
STA 858+85.00, 32.38' RT	1	
STA 859+39.08, 70.00' RT	1	
STA 860+09.91, 85.00' RT	1	
STA 860+10.98, 33' RT		1
STA 860+84.00, 50.00' RT	1	
STA 864+40.92, 50.00' RT	1	
STA 865+00.00, 50.00' RT	1	
STA 866+00.00, 25.99' RT	1	
TOTAL	7	1

CONTROLLED LOW-STRENGTH MATERIAL	
LOCATION	CU YD
STA 861+80.00 to STA 861+90, 14.00' LT	3.3
TOTAL	3.3



USER NAME = dmeyer
 DESIGNED - JJO
 DRAWN - JJO
 PLOT SCALE = 2.0000' / in.
 CHECKED - JML
 DATE = 08/10/12

DESIGNED - JJO
 DRAWN - JJO
 CHECKED - JML
 DATE = 08/10/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	19BR	FORD	61	12
CONTRACT NO. 66A12				
ILLINOIS FED. AID PROJECT				