

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY URBAN TWO-LANE ROADWAY 90% FEDERAL 10% STATE 0011	S.N. 010-0291 70% STATE 30% CITY 0021
51100100	SLOPE WALL 4 INCH	SQ YD	495	
51200959	FURNISHING METAL SHELL PILES 14" X 0.312"	FOOT	1846	
51202305	DRIVING PILES	FOOT	1846	
51203200	TEST PILE METAL SHELLS	EACH	3	
51204650	PILE SHOES	EACH	41	
51500100	NAME PLATES	EACH	1	
52100520	ANCHOR BOLTS, 1"	EACH	36	
52100530	ANCHOR BOLTS, 1 1/4"	EACH	18	
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	6	
542A0241	PIPE CULVERTS, CLASS A, TYPE 1 36"	FOOT	231	
54213447	END SECTIONS 12"	EACH	2	
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	4	
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	2	
54248510	CONCRETE COLLAR	CU YD	0.5	

FILE NAME * #FILE#	USER NAME * #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE. 57	SECTION 110-32HB-21BY	COUNTY CHAMPAIGN	TOTAL SHEETS 81	SHEET NO. 6
		DRAWN -	REVISED -		SCALE:	SHEET NO. 4 OF 8 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 70109	
		CHECKED -	REVISED -									
		DATE -	REVISED -									