

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY I-74 RURAL HSIP 90% FEDERAL 10% STATE 0021
20200100	EARTH EXCAVATION	CU YD	3010
20400800	FURNISHED EXCAVATION	CU YD	13720
25000210	SEEDING, CLASS 2A	ACRE	15.75
25000350	SEEDING, CLASS 7	ACRE	15.75
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1417.5
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1417.5
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1417.5
25100115	MULCH, METHOD 2	ACRE	15.75
25100630	EROSION CONTROL BLANKET	SQ YD	80
28000305	TEMPORARY DITCH CHECKS	FOOT	1254
28000500	INLET AND PIPE PROTECTION	EACH	47
28100201	STONE RIPRAP, CLASS A1	TON	285
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5509
50104400	CONCRETE HEADWALL REMOVAL	EACH	156

CODE NO.	ITEM	UNIT	TOTAL QUANTITY I-74 RURAL HSIP 90% FEDERAL 10% STATE 0021
54217690	REINFORCED CONCRETE PIPE TEE, 30" PIPE WITH 24" RISER	EACH	2
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	21
54246405	INLET BOX, STANDARD 542531	EACH	18
54248510	CONCRETE COLLAR	CU YD	16.5
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	82
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	85
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	14
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	25
55100900	STORM SEWER REMOVAL 18"	FOOT	16
55101200	STORM SEWER REMOVAL 24"	FOOT	30
55101400	STORM SEWER REMOVAL 30"	FOOT	13
55101600	STORM SEWER REMOVAL 36"	FOOT	36
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	119

* SPECIALTY ITEM

McDonough-Whitlow, P.C.
 138 East Wood Street
 Hillsboro, IL 62049
 Phone: 217.532.9233
 Fax: 217.532.6300
 PROFESSIONAL ENGINEER No. 181-002754

FILE NAME : D78966-003-500.dgn	USER NAME : JLM	DESIGNED - JAH	REVISED -
		DRAWN - JLM	REVISED -
		CHECKED - TMM	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	MEDIAN CABLE 2012-2	VERMILION	120	3
CONTRACT NO. 70967				
ILLINOIS FED. AID PROJECT				