



DESCRIPTION	STATION	NORTHING	EASTING
PT #1009	1132+17.27	1,259,253.0664	1,101,976.6492
STA. EQ. #540	1224+77.59(BK) 1224+63.88(AH)	1,259,440.4663	1,111,235.0758
PC #1010	1353+43.86	1,259,707.6970	1,124,112.2877
PI #616	1360+28.71	1,259,721.8282	1,124,796.9892
PT #1011	1367+13.39	1,259,762.2569	1,125,480.6421
PC #1012	1556+27.08	1,260,878.7380	1,144,361.3480
PI #617	1562+45.08	1,260,915.2180	1,144,978.2710
PT #1013	1568+62.77	1,260,917.7970	1,145,596.2662

BENCHMARKS

BM 4906-1
 1.72' LT STA. 1606+98.16 EL. 639.69'
 TO REACH FROM THE INTERSECTION OF I-74 AND
 THE OVERHEAD AT OAKWOOD GO EAST ON I-74 FOR
 1.85 MILES TO THE MARK ON THE LEFT. SAID MARK
 IS A CHISELED SQUARE SET ON THE TOP CENTER
 OF THE NORTH HEADWALL OF A DROP BOX IN THE
 MEDIAN. SOUTH OF REST AREA.

NOTE:
 ADDITIONAL TEMPORARY BENCHMARKS REQUIRED BY THE
 RESIDENT ENGINEER WILL BE SET BY DISTRICT 5 SURVEY
 PERSONNEL PRIOR TO CONSTRUCTION. PLEASE CONTACT
 BETH SABLONNY AT 217-465-7282.

McDonough-Whitlow, P.C.
 Consulting Engineers & Land Surveyors
 138 East Wood Street
 Hillisboro, IL 62049
 Phone: 217.532.9233
 Fax: 217.532.6300
 PROFESSIONAL DESIGN NO. 184-002754

FILE NAME = D570967-xxx-ALIGNMENT & BM	USER NAME = MRM	DESIGNED - ---	REVISED - -
	PLOT SCALE = 50	DRAWN - MRM	REVISED - -
	PLOT DATE = 4/4/2012	CHECKED - TMM	REVISED - -
		DATE - _____	REVISED - -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

ALIGNMENT AND BENCH MARKS

SCALE: SHEET NO. 1 OF 2 SHEETS STA. 1132+17.07 TO STA. 1370+00.00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	MEDIAN CABLE 2012-2	VERMILION	120	11
CONTRACT NO. 70967			ILLINOIS FED. AID PROJECT	