

LOCATION OF PROJECT: FAP 0559 IL RTE 58 (GOLF ROAD) AT NEW WILKE ROAD, COOK COUNTY
 FUNDS: NEW WILKE RD - 75%FED(STP/STU) 25%LOCAL(ERP), GOLF RD - STP/STU 75%FED 25%LOCAL, URBAN
 CONSTRUCTION TYPE CODE 0003

* SPECIALTY ITEM

CODE NO	DESCRIPTION	UNIT	TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	570
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	18
20101000	TEMPORARY FENCE	FOOT	1560
20101200	TREE ROOT PRUNING	EACH	14
20200100	EARTH EXCAVATION	CU YD	11992
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	3932
20800150	TRENCH BACKFILL	CU YD	1747
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	14138
* 21101815	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	10115
* 21101885	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	1958
* 25000210	SEEDING, CLASS 2A	ACRE	2.79
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	225
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	225
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	225
* 25100830	EROSION CONTROL BLANKET	SQ YD	12072
* 25200200	SUPPLEMENTAL WATERING	UNIT	47
* 28900250	TEMPORARY EROSION CONTROL SEEDING	POUND	48
28000305	TEMPORARY DITCH CHECKS	FOOT	16
28000400	PERIMETER EROSION BARRIER	FOOT	364
28000510	INLET FILTERS	EACH	121
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	4418
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	31788

CODE NO	DESCRIPTION	UNIT	TOTAL QUANTITY
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	836
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	410
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	1114
40600180	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	530
40600300	AGGREGATE (PRIME COAT)	TON	4
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5
40600835	LEVELING BINDER (MACHINE METHOD), N70	TON	85
40600882	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	83
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	240
40603585	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	150
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	54
42000401	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	4417
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 18" (JOINTED)	SQ YD	23400
42001300	PROTECTIVE COAT	SQ YD	13810
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	703
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	15534
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	1060
42400800	DETECTABLE WARNINGS	SQ FT	287
44000100	PAVEMENT REMOVAL	SQ YD	20103
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2348
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	13560
44000800	SIDEWALK REMOVAL	SQ FT	11996

FILE NAME =

USER NAME =

DESIGNED - BLL
 DRAWN - PMM

REVISED
 REVISED

PLCT SCALE = 2"

CHECKED - JGS
 DATE - 8/06/12

REVISED
 REVISED

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

IL RTE 58 (GOLF ROAD) AND NEW WILKE ROAD IMPROVEMENTS
 SUMMARY OF QUANTITIES

F.A.P. RTE. 0559	SECTION 00-00078-00-CH	COUNTY COOK	TOTAL SHEETS 116	SHEET NO. 3
SCALE: N.T.S.			SHEET NO. 1 OF 5 SHEETS STA. TO STA.	
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

CONTRACT NO. 83735