LOCATION OF PROJECT: FAP 0559 IL RTE 58 (GOLF ROAD) AT NEW WILKE ROAD, COOK COUNTY
FUNDS: NEW WILKE RD – 75%FED(STP/STU) 25%LOCAL(ERP), GOLF RD – STP/STU 75%FED 25%LOCAL, URBAN
CONSTRUCTION TYPE CODE 0003

*** SPECIALTY ITEM**

	CODE NO	DESCRIPTION	UNIT	TOTAL QUANTITY
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	8926
*	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	119
*	80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	2
*	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	3610
*	81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	189
*	81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	156
*	81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	826
*	81400100	HANDHOLE	EACH	11
*	81400200	HEAVY-DUTY HANDHOLE	EACH	8
*	81400300	DOUBLE HANDHOLE	EACH	4
*	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1
*	86200200	UNINTERRUPTABLE POWER SUPPLY, STANDARD	EACH	2
*	86400100	TRANSCEIVER - FIBER OPTIC	EACH	2
*	87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	3063
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2594
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	4178
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	6142
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	3380
*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	6973.5
*	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	260
*	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1750
*	87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	3

	CODE NO	DESCRIPTION	UNIT	TOTAL QUANTITY
*	87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	2
*	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	6
*	87700150	STEEL MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	1
*	87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1
*	87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1
*	87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1
*	87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1
*	87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1
*	87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	2
*	87700300	STEEL MAST ARM ASSEMBLY AND POLE, 52 FT.	EACH	1
*	87700340	STEEL MAST ARM ASSEMBLY AND POLE, 58 FT.	EACH	1
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	48
*	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	8
*	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	30
*	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	105
*	87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	21
*	87900260	DRILL EXISTING HANDHOLE	EACH	1
*	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	22
*	88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3
*	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4
*	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	10
*	88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION BRACKET MOUNTED	EACH	1