ORIGINAL SURVEY		BY	DATE
	SURVEYED		
NOTE BOOK	PLOTTED		
	TEMPLATE		
NO.	AREAS		
	AREAS CHECKED		

FINAL SURVEY		BY	DATE
	SURVEYED		
NOTE BOOK	PLOTTED		
	TEMPLATE		
NO.	AREAS		
	AREAS CHECKED		

FILE NAME = N:\DGN\ROWS\98-06HRP2A\Civil\XSROUF9893123A.dgn

PLOT SCALE = 1.0' / IN.

PLOT DATE = 6/25/2002

JOHN WOHF

DESIGNED - BLL

DRAWN - PMM

CHECKED - JGS

DATE 08/06/12

REVISED -

REVISED -

REVISED -

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL RTE 58 (GOLF ROAD) AND NEW WILKE ROAD IMPROVEMENTS
CROSS SECTIONS
IL RTE 58 (GOLF ROAD)

SCALES: 1OH 5V

SHEET NO. OF SHEETS

STA. 92+50.0

TC STA. 94+00.0

F.A.P. RTE 3559

SECTION 00-00078-00-CH

FED. ROAD DIST. NO.

ILLINOIS FED. AID PROJECT

COUNTY COOK

CONTRACT NO. 63735

TOTAL SHEETS NO. 115 101

94+00.0

STAGE 2 & 3 CONSTRUCTION | STAGE 1 CONSTRUCTION | PGL

EXISTING ROW

2.0% | 5.0% | 692.16 | 692.25 | 2.0% | 692.73 | 3.0% | 4.9% | 692.88 | 1.5% | 692.73 | 2.0% | 692.25 | 2.5% | 692.07 | 4% | 693.25 | 2.0%

EX 16"x48" SS | EX 20" WATER

STG II/III CUT=182
STG II/III FILL=6
STG II/III UNSUIT TS=0
STG II/III UNSUIT ASI (CY)=96

STG I CUT=67
STG I FILL=0
STG I UNSUIT TS=9
STG I UNSUIT ASI (CY)=35

EX 42" SS

EX 8" GAS

93+95.3

LOIS DRIVE

STAGE 2 & 3 CONSTRUCTION | STAGE 1 CONSTRUCTION | PGL

EXISTING ROW

2.0% | 5.0% | 692.18 | 692.27 | 2.0% | 692.76 | 3.0% | 4.5% | 692.88 | 1.5% | 692.73 | 2.0% | 692.26 | 2.5% | 692.09 | 4% | 693.27 | 2.0%

EX 16"x48" SS | EX 20" WATER

STG II/III CUT=197
STG II/III FILL=6
STG II/III UNSUIT TS=0
STG II/III UNSUIT ASI (CY)=95

STG I CUT=66
STG I FILL=0
STG I UNSUIT TS=9
STG I UNSUIT ASI (CY)=35

EX 42" SS

EX 8" GAS

93+50.0

STAGE 2 & 3 CONSTRUCTION | STAGE 1 CONSTRUCTION | PGL

EXISTING ROW

2.0% | 692.35 | 692.46 | 2.0% | 692.84 | 3.0% | 2.8% | 692.99 | 692.84 | 2.0% | 692.46 | 2.5% | 692.33 | 4% | 693.50 | 2.0%

EX 16"x48" SS | EX 20" WATER

STG II/III CUT=45
STG II/III FILL=12
STG II/III UNSUIT TS=7
STG II/III UNSUIT ASI (CY)=40

STG I CUT=44
STG I FILL=2
STG I UNSUIT TS=8
STG I UNSUIT ASI (CY)=33

EX 42" SS

EX 8" GAS

93+00.0

STAGE 2 & 3 CONSTRUCTION | STAGE 1 CONSTRUCTION | PGL

EXISTING ROW

2.0% | 692.46 | 692.54 | 2.0% | 693.02 | 3.0% | 1.7% | 693.02 | 2.0% | 692.54 | 692.47 | 3.5% | 693.75 | 2.0% | 6.8%

EX 12" WATER | EX 16"x48" SS | EX 20" WATER

STG II/III CUT=31
STG II/III FILL=16
STG II/III UNSUIT TS=5
STG II/III UNSUIT ASI (CY)=37

STG I CUT=37
STG I FILL=1
STG I UNSUIT TS=6
STG I UNSUIT ASI (CY)=31

EX 42" SS

EX 8" GAS

92+50.0

STAGE 2 & 3 CONSTRUCTION | STAGE 1 CONSTRUCTION | PGL

EXISTING ROW

7.0% | 692.37 | 692.46 | 2.0% | 692.94 | 3.0% | 2.1% | 692.94 | 2.0% | 692.46 | 3.5% | 694.00 | 2.0% | 2.0%

EX 12" WATER | EX 16"x48" SS | EX 20" WATER

STG II/III CUT=31
STG II/III FILL=12
STG II/III UNSUIT TS=5
STG II/III UNSUIT ASI (CY)=37

STG I CUT=32
STG I FILL=8
STG I UNSUIT TS=6
STG I UNSUIT ASI (CY)=28

EX 42" SS