

ITEM NUMBER	ITEM	UNIT	QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	140
20200100	EARTH EXCAVATION	CU YD	3080
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	250
20400800	FURNISHED EXCAVATION	CU YD	328
20700110	POROUS GRANULAR EMBANKMENT	TON	100
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	300
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4511
25200100	SODDING	SQ YD	4511
28000510	INLET FILTERS	EACH	125
31100100	SUBBASE GRANULAR MATERIAL, TYPE A	TON	2310
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	4421
35100100	AGGREGATE BASE COURSE, TYPE A	TON	1532
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	245
35650500	BASE COURSE WIDENING 10"	SQ YD	60
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	696
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	852
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2220
40600837	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70	TON	89
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	278
40603230	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	317
40603560	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N50	TON	793
40603565	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N70	TON	2111
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	0
42001300	PROTECTIVE COAT	SQ YD	4213
42000200	PORTLAND CEMENT CONCRETE PAVEMENT 7"	SQ YD	283
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	2492
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	70721
42400800	DETECTABLE WARNINGS	SQ FT	1175
44000100	PAVEMENT REMOVAL	SQ YD	18678
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1781
44000163	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/2"	SQ YD	273
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	10441
44000300	CURB REMOVAL	FOOT	2285
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	10291
44000600	SIDEWALK REMOVAL	SQ FT	114083
44200909	CLASS B PATCHES, TYPE III, 6 INCH	SQ YD	41
44200911	CLASS B PATCHES, TYPE IV, 6 INCH	SQ YD	134
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	7
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	396
44200998	CLASS B PATCHES, TYPE III, 12 INCH	SQ YD	20
44201000	CLASS B PATCHES, TYPE IV, 12 INCH	SQ YD	472
44201031	CLASS B PATCHES, TYPE II, 15 INCH	SQ YD	140
44201035	CLASS B PATCHES, TYPE III, 15 INCH	SQ YD	39
44201037	CLASS B PATCHES, TYPE IV, 15 INCH	SQ YD	2721
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	10
44201377	CLASS C PATCHES, TYPE II, 12 INCH	SQ YD	49
44201415	CLASS C PATCHES, TYPE II, 15 INCH	SQ YD	28
44201419	CLASS C PATCHES, TYPE III, 15 INCH	SQ YD	15
54248510	CONCRETE COLLAR	CU YD	0.4
50901760	PIPE HANDRAIL	FOOT	141
550A0050	STORM SEWERS, CLASS A, TYPE 1 1/2"	FOOT	1021
550A0340	STORM SEWERS, CLASS A, TYPE 2 1/2"	FOOT	1049
550A0430	STORM SEWERS, CLASS A, TYPE 2 3/4"	FOOT	84
55100400	STORM SEWER REMOVAL 10"	FOOT	50
55100500	STORM SEWER REMOVAL 12"	FOOT	705
55100700	STORM SEWER REMOVAL 15"	FOOT	16
55100900	STORM SEWER REMOVAL 18"	FOOT	4
55101200	STORM SEWER REMOVAL 24"	FOOT	51
55101400	STORM SEWER REMOVAL 30"	FOOT	43
55101900	STORM SEWER REMOVAL 36"	FOOT	9

ITEM NUMBER	ITEM	UNIT	QUANTITY
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	1926
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	28
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	6
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	5
60255500	MANHOLES TO BE ADJUSTED	EACH	21
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2
60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2
60500040	REMOVING MANHOLES	EACH	10
60500060	REMOVING INLETS	EACH	53
60600605	CONCRETE CURB, TYPE B	FOOT	1392
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	12952
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	82
60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	426
61141600	STORM SEWERS (SPECIAL), 48"	FOOT	0
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	255
66900450	SPECIAL WASTE PLANS AND REPORTS	I SUM	1
66900530	SOIL DISPOSAL ANALYSIS	EACH	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24
67100100	MOBILIZATION	I SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	24
70300100	SHORT TERM PAVEMENT MARKING	FOOT	4300
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	63
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	26537
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	514
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5832
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6519
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	10459
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	281
78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	900
78006100	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	553
78006140	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2813
78006180	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	433
78300100	PAVEMENT MARKING REMOVAL	SQ FT	3783
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	14028
81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	190
81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	533
81400100	HANDHOLE	EACH	22
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	12
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	3
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	37955
81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	5701
82500370	LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 200AMP	EACH	3
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	590
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	35
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	3
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	6046
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	857
87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR	FOOT	1299
87502510	TRAFFIC SIGNAL POST, GALVANIZED STEEL 17 FT.	EACH	9
87702840	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 22 FT.	EACH	1
87702860	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 26 FT.	EACH	2
87702870	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 28 FT.	EACH	1
87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 36 FT.	EACH	1
87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT.	EACH	1
87702960	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 46 FT.	EACH	1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	27

\* SPECIALTY ITEMS