

EARTHWORK SUMMARY						
LOCATION	20200100	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	EMBANKMENT	20400800	20201200	66900200
	EARTH EXCAVATION			BALANCE WASTE (+) OR SHORTAGE (-)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	NON-SPECIAL WASTE DISPOSAL
	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
ADAMS ST.						
140+65.00	146+00.00	290	218	392	-174	0
146+00.00	149+96.07	207	155	101	54	0
149+96.07	154+40.00	249	187	112	75	0
154+40.00	158+75.00	164	123	179	-56	0
158+75.00	165+30.00	327	245	203	42	0
JEFFERSON AVE						
240+25.00	245+75.00	171	128	355	-227	0
245+75.00	250+00.00	115	86	258	-172	0
250+00.00	255+20.00	207	155	339	-184	0
PERSIMMON ST						
593+60.00	596+70.00	84	63	158	-95	0
598+25.00	599+74.71	31	23	44	-21	0
MAPLE ST.						
248+60.00	249+65.00	100	75	28	47	0
698+10.00	701+54.15	65	49	67	-18	0
ELM ST.						
746+15.00	749+15.00	248	186	77	109	0
OAK ST.						
793+65.00	796+60.00	115	86	50	36	0
798+15.00	799+90.53	95	71	53	18	0
STATE ST.						
898+45.00	901+00.45	63	47	118	-71	0
903+15.00	906+50.37	485	364	116	248	0
WALNUT ST.						
950+00.00	952+42.82	65	49	46	3	0
COMMERCIAL ST.						
1708+00.00	1716+70.00	0	0	0	0	0
CONTINGENCY						
		0	0	0	0	250
TOTAL						
		3380	1382	1710	328	250

ADJUSTMENT SCHEDULE						
LOCATION	STATION	OFFSET	LT/RT	60255500	60255800	60260400
				MANHOLES TO BE ADJUSTED	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID
				EACH	EACH	EACH
ADAMS STREET						
	141+52.83	23.53	LT	1		
	145+67.15	22.63	LT	1		
	150+12.88	39.56	LT	1		
	150+13.41	3.84	LT	1		
	154+31.75	21.99	RT	1		
	154+39.11	31.47	LT	1		
	162+80.41	35.39	LT	1		
	163+08.88	23.66	RT	1		
JEFFERSON AVENUE						
	245+39.88	29.08	LT			1
	245+96.53	47.95	RT		1	
	246+20.40	28.45	RT		1	
	250+09.94	12.44	LT	1		
	254+56.43	8.80	LT	1		
OAK STREET						
	793+37.82	16.50	RT	1		
	796+92.35	14.92	LT	1		
	799+77.58	21.40	RT			1
WALNUT STREET						
	951+00.00	0.60	RT	1		
	951+06.88	0.30	RT	1		
	952+29.40	0.10	LT	1		
COMMERCIAL STREET						
	1715+24.45	38.90	LT	1		
	1715+38.20	35.60	LT	1		
	1716+52.80	18.90	RT			1
BEGIN						
	STATION		END			
OAK STREET						
	793+65.00	TO	796+60.00	1		
	796+15.00	TO	799+90.53	0		
STATE STREET						
	898+45.00	TO	901+00.45	1		
	903+15.00	TO	907+05.86	2		
TOTAL						
				21	2	3



1 COMMERCIAL STREET REMOVED FROM PROJECT

NOTES:
1. FOR STORM SEWER QUANTITIES, SEE PROPOSED DRAINAGE SHEETS