	ITEM NUMBER	ITEM	UNIT	QUANTITY
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	158
	20200100	EARTH EXCAVATION	CU YD	4718
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	250
	20400800	FURNISHED EXCAVATION	CU YD	800
	20700110	POROUS GRANULAR EMBANKMENT	TON	100
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	300
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4545
*	25200100	SODDING	SQ YD	4545
	28000510	INLET FILTERS	EACH	142
	31100100	SUBBASE GRANULAR MATERIAL, TYPE A	TON	4985
	31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	4616
	35100100	AGGREGATE BASE COURSE, TYPE A	TON	1617
	35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	245
	35650500	BASE COURSE WIDENING 10"	SQ YD	60
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	696
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	895
	40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2240
	40600837	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70	TON	89
	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	294
	40603230	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	333
	40603560	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N50	TON	803
	40603565	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N70	TON	2111
	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	56
	42001300	PROTECTIVE COAT	SQ YD	8308
	42000200	PORTLAND CEMENT CONCRETE PAVEMENT 7"	SQ YD	3795
	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	2631
	42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	74846
	42400800	DETECTABLE WARNINGS	SQ FT	1517
	44000100	PAVEMENT REMOVAL	SQ YD	21904
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1781
	44000163	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/2"	SQ YD	273
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	10441
	44000300	CURB REMOVAL	FOOT	2317
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	10850
	44000600	SIDEWALK REMOVAL	SQ FT	116767
	44200909	CLASS B PATCHES, TYPE III, 6 INCH	SQ YD	41
	44200911	CLASS B PATCHES, TYPE IV, 6 INCH	SQ YD	134
	44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	7
	44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	396
	44200998	CLASS B PATCHES, TYPE III, 12 INCH	SQ YD	20
	44201000	CLASS B PATCHES, TYPE IV, 12 INCH	SQ YD	472
	44201031	CLASS B PATCHES, TYPE II, 15 INCH	SQ YD	140
	44201035	CLASS B PATCHES, TYPE III, 15 INCH	SQ YD	39
	44201037	CLASS B PATCHES, TYPE IV, 15 INCH	SQ YD	2721
	44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	10
	44201377	CLASS C PATCHES, TYPE II, 12 INCH	SQ YD	49
	44201415	CLASS C PATCHES, TYPE II, 15 INCH	SQ YD	28
	44201419	CLASS C PATCHES, TYPE III, 15 INCH	SQ YD	15
	54248510	CONCRETE COLLAR	CU YD	0
	50901760	PIPE HANDRAIL	FOOT	89
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	1021
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1698
	550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	84
	55100400	STORM SEWER REMOVAL 10"	FOOT	50
	55100500	STORM SEWER REMOVAL 12"	FOOT	938
	55100700	STORM SEWER REMOVAL 15"	FOOT	16
	55100900	STORM SEWER REMOVAL 18"	FOOT	4
	55101200	STORM SEWER REMOVAL 24"	FOOT	51
	55101400	STORM SEWER REMOVAL 30"	FOOT	43
	55101900	STORM SEWER REMOVAL 48"	FOOT	21

	ITEM NUMBER	ITEM	UNIT	QUANTITY
	59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	3046
	60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	28
	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5
	60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5
	60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3
	60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	6
	60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	5
	60255500	MANHOLES TO BE ADJUSTED	EACH	21
	60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2
	60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3
	60500040	REMOVING MANHOLES	EACH	10
	60500060	REMOVING INLETS	EACH	56
	60600605	CONCRETE CURB, TYPE B	FOOT	1601
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	13878
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	82
	60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	999
	61141600	STORM SEWERS (SPECIAL), 48"	FOOT	21
*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	255
*	66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1
*	66900530	SOIL DISPOSAL ANALYSIS	EACH	1
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24
	67100100	MOBILIZATION	L SUM	1
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	24
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	4300
	70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	63
	70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	26537
	70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	514
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5832
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7113
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	11660
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	300
*	78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	900
*	78006100	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	576
*	78006140	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	3039
*	78006180	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	483
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	3783
*	81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	14742
*	81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	190
*	81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	533
*	81400100	HANDHOLE	EACH	22
*	81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	12
*	81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	3
*	81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	37854
*	81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	8016
*	82500370	LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 200AMP	EACH	3
*	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	645
*	83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	35
*	85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	3
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	6046
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	857
*	87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR	FOOT	1299
*	87502510	TRAFFIC SIGNAL POST, GALVANIZED STEEL 17 FT.	EACH	9
*	87702840	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 22 FT.	EACH	1
*	87702860	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 26 FT.	EACH	2
*	87702870	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 28 FT.	EACH	1
*	87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 36 FT.	EACH	1
*	87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT.	EACH	1
*	87702960	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 46 FT.	EACH	1
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	27

* SPECIALTY ITEMS