PLANTING SCHEDULE - ADAMS STREET (MAPLE TO OAK)

	LOCATION	STATION	146+45.00	148+45.00	146+86.25	147+20.75	147+20.75	147+55.25	147+89.75	148+24.25	148+24.25	148+58.75	148+93.25	148+93.25	149+27.75	149+62.25	149+68.0	150+31.25	150+55.0	151+00.25	151+00.27	151+34.75	151+34.77	151+69.25	151+69.27	152+03.78	152+38.28	152+72.78	152+72.77	153+07.25	153+07.25	153+41.77	153+41.75	153+83.00	153+83.00	TOTALS
		OFFSET	20.2'	25.2'	26.9'	28.9'	23.9'	28.9'	28.9'	28.9'	23.9'	28.9'	28.9'	23.9'	28.9'	23.9'	25.6'	23.9'	25.3'	23.9'	28.9'	23.9'	28.9'	23.9'	28.9'	28.9'	28.9'	23.9'	28.9'	28.9'	23.9'	28.9'	23.7'	20.2'	25.2'	
		LT/RT	RT	LT	LT	LT	RT	LT	LT	LT	RT	LT	LT	RT	LT	RT	LT	RT	LT	RT	LT	RT	LT	RT	LT	LT	LT	RT	LT	LT	RT	LT	RT	RT	LT	
A2001916	TREE, ACER SACCHARUM LEGACY (LEGACY SUGAR MAPLE), 2" CALIPER, BALLED AND BURLAPPED																			1			1	1		1			1		1	1				7
A2005616	TREE, OSTRYA VIRGINIANA (AMERICAN HOPHORNBEAM), 2" CALIPER, BALLED AND BURLAPPED				1		1	1		1			1	1				1			1	1			1		1	1		1			1			14
A2007716	TREE, TAXODIUM DISTICHUM SHAWNEE BRAVE (SHAWNEE BRAVE BALD CYPRESS), 2" CALIPER, BALLED AND BURLAPPED					1			1		1	1			1	1																				6
C2C00324	SHRUB, ARONIA MELANOCARPA IROQUOIS BEAUTY (IROQUOIS BEAUTY BLACK CHOKEBERRY), 2' HEIGHT, CONTAINER				8		8	8		8			8	8				8			8	8			8		8	8		8			8			112
C2002636	SHRUB, EUONYMUS ALATA COMPACTA (DWARF WINGED EUONYMUS), 3' HEIGHT, BALLED AND BURLAPPED																5		4																	9
C2C04075	SHRUB, PHYSOCARPA OPULIFOLIUS DONNA MAY (LITTLE DEVIL NINEBARK), 18" HEIGHT, CONTAINER																			4			4	4		4			4		4	4				28
C2C056G3	SHRUB, RHUS AROMATICA GRO-LOW (GRO-LOW FRAGRANT SUMAC), CONTAINER GROWN, 3-GALLON																																	6	8	14
C2C11752	SHRUB, VIBURNUM DENTATUM CHRISTORS (BLUE MUFFIN VIBURNUM), 24" HEIGHT, CONTAINER		4	5																																9
D2003524	EVERGREEN, TAXUS X MEDIA DENSIFORMIS (DENSE YEW), 2' WIDTH, BALLED AND BURLAPPED					4			4		4	4			4	4																				24
K0012990	PERENNIAL PLANTS, AMSONIA HUBRICHTII (ARKANSAS BLUE-STAR), GALLON POT		24	30																																54
K0012975	PERENNIAL PLANTS, COREOPSIS VERTICILLATA ZAGREB (ZAGREB THREADLEAF COREOPSIS), 4" POT																																	38	39	77
K0012990	PERENNIAL PLANTS, GERANIUM X ROZANNE (ROZANNE CRANESBILL), GALLON POT				12		12	12		12			12	12				12			12	12			12		12	12		12			12			168
K0012990	PERENNIAL PLANTS, HEMEROCALLIS STELLA DE ORO (STELLA DE ORO DAYLILY), GALLON POT					12			12		12	12			12	12																				72
K0012990	PERENNIAL PLANTS, HEMEROCALLIS STRAWBERRY CANDY (STRAWBERRY CANDY DAYLILY), GALLON POT		37	36																																73
K0012993	PERENNIAL PLANTS, MISCANTHUS SINENSIS GRACILLIMUS (GRACILLIMUS MAIDEN GRASS), 3 GALLON POT																																	12	8	20
K0012990	PERENNIAL PLANTS, MISCANTHUS SINENSIS LITTLE KITTEN (LITTLE KITTEN MAIDEN GRASS), GALLON POT																			12			12	12		12			12		12	12				84
K0012990	PERENNIAL PLANTS, NEPETA X FAASENII WALKERS LOW (WALKERS LOW CATMINT), GALLON POT																27		31																	58
K0012993	PERENNIAL PLANTS, PANICUM VIRGATUM SHENENDOAH (BURGUNDY SWITCH GRASS), 3 GALLON POT		9	10																																19
K0012990	PERENNIAL PLANTS, PEROVSKIA ATRIPLICIFOLIA LITTLE SPIRE (LITTLE SPIRE RUSSIAN SAGE), GALLON POT																																	32	35	67
K0012990	PERENNIAL PLANTS, SPOROBOLUS HETEROLEPIS (PRAIRIE DROPSEED), GALLON POT																30		32																	62

PLANTING SCHEDULE - ADAMS STREET (OAK TO STATE)

	LOCATION	STATION	155+00.0	155+00.0	155+82.62	156+17.12	156+51.62	156+51.62	156+86.12	156+86.12	157+20.62	157+20.62	157+55.12	157+55.12	157+89.62	157+89.62	158+20.0	158+24.12	158+72.84	TOTALS
		OFFSET	21.5'	20.2'	23.9'	23.9'	21.4'	23.9'	21.4'	23.9'	21.4'	23.9'	21.4'	23.9'	21.4'	23.9'	20.0'	21.4'	21.4'	
		LT/RT	LT	RT	RT	RT	LT	RT	LT	RT	LT	RT	LT	RT	LT	RT	RT	LT	LT	
A2000116	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 2" CALIPER, BALLED AND BURLAPPED				1			1	1			1	1			1				6
A2001916	TREE, ACER SACCHARUM LEGACY (LEGACY SUGAR MAPLE), 2" CALIPER, BALLED AND BURLAPPED					1	1			1	1			1	1					6
C2C01812	SHRUB, CORNUS SANGUINEA ARCTIC SUN (ARCTIC SUN DOGWOOD), 2' HEIGHT, CONTAINER				4			4	4			4	4			4		4		28
C2002636	SHRUB, EUONYMUS ALATA COMPACTA (DWARF WINGED EUONYMUS), 3' HEIGHT, BALLED AND BURLAPPED																		1	1
C2C04075	SHRUB, PHYSOCARPA OPULIFOLIUS DONNA MAY (LITTLE DEVIL NINEBARK), 18" HEIGHT, CONTAINER					4	4			4	4			4	4					24
C2C10218	SHRUB, SPIREA JAPONICA LITTLE PRINCESS (LITTLE PRINCESS JAPANESE SPIREA), 18" HEIGHT, CONTAINER		6	9																15
C2C11752	SHRUB, VIBURNUM DENTATUM CHRISTORS (BLUE MUFFIN VIBURNUM), 24" HEIGHT, CONTAINER			6																6
K0012990	PERENNIAL PLANTS, AMSONIA HUBRICHTII (ARKANSAS BLUE-STAR), GALLON POT			25																25
K0012990	PERENNIAL PLANTS, ECHINACEA PURPUREA KIM'S KNEE HIGH (KIM'S KNEE HIGH PURPLE CONEFLOWER), GALLON POT				12			12	12			12	12			12		16		88
K0012993	PERENNIAL PLANTS, MISCANTHUS SINENSIS GRACILLIMUS (GRACILLIMUS MAIDEN GRASS), 3 GALLON POT																		2	2
K0012990	PERENNIAL PLANTS, MISCANTHUS SINENSIS LITTLE KITTEN (LITTLE KITTEN MAIDEN GRASS), GALLON POT					12	12			12	12			12	12					72
K0012993	PERENNIAL PLANTS, PANICUM VIRGATUM SHENENDOAH (BURGUNDY SWITCH GRASS), 3 GALLON POT		6	10																16
K0012975	PERENNIAL PLANTS, PHLOX SUBULATA EMERALD PINK (EMERALD PINK CREEPING PHLOX), 4" POT		38	62													28			128
K0012990	PERENNIAL PLANTS, RUDBECKIA FULGIDA GOLDSTRUM (GOLDSTURM BLACK -EYED SUSAN), GALLON POT																14		12	26
K0012990	PERENNIAL PLANTS, SPOROBOLUS HETEROLEPIS (PRAIRIE DROPSEED), GALLON POT																8		6	14

PLANTING SCHEDULE - ADAMS STREET (STATE TO WALNUT)

	LOCATION	STATION	158+72.84	159+34.23	159+50.00	159+68.73	160+03.23	160+36.02	160+37.73	160+72.52	160+72.23	161+06.88	161+06.99	161+41.36	161+75.86	162+10.36	162+10.42	162+44.88	162+55.65	162+74.0	TOTALS
		OFFSET	21.4'	21.4'	24.1'	21.4'	21.4'	21.4'	23.9'	21.4'	23.9'	23.9'	21.4'	23.9'	23.9'	23.9'	21.4'	23.9'	21.5'	20.2'	
		LT/RT	LT	LT	RT	LT	LT	LT	RT	LT	RT	RT	LT	RT	RT	RT	LT	RT	LT	RT	
A2000116	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 2" CALIPER, BALLED AND BURLAPPED					1		1			1		1	1		1					6
A2004512	TREE, GINKGO BILOBA AUTUMN GOLD (AUTUMN GOLD GINKGO), 2" CALIPER, BALLED AND BURLAPPED				1		1		1	1		1			1		1				7
C2C01812	SHRUB, CORNUS SANGUINEA ARCTIC SUN (ARCTIC SUN DOGWOOD), 2' HEIGHT, CONTAINER					4		4			4		4	4		4					24
C2002636	SHRUB, EUONYMUS ALATA COMPACTA (DWARF WINGED EUONYMUS), 3' HEIGHT, BALLED AND BURLAPPED		1																		1
C2C056G3	SHRUB, RHUS AROMATICA GRO-LOW (GRO-LOW FRAGRANT SUMAC), CONTAINER GROWN, 3-GALLON				10																10
C2C06724	SHRUB, ROSA PAVEMENT DWARF (DWARF PAVEMENT ROSE), 24" HEIGHT, CONTAINER			6	8		8		8	8		8			8		8	6			70
C2C10218	SHRUB, SPIREA JAPONICA LITTLE PRINCESS (LITTLE PRINCESS JAPANESE SPIREA), 18" HEIGHT, CONTAINER				16																16
K0012990	PERENNIAL PLANTS, AMSONIA HUBRICHTII (ARKANSAS BLUE-STAR), GALLON POT																		12		12
K0012975	PERENNIAL PLANTS, COREOPSIS VERTICILLATA ZAGREB (ZAGREB THREADLEAF COREOPSIS), 4" POT				22																22
K0012990	PERENNIAL PLANTS, ECHINACEA PURPUREA KIM'S KNEE HIGH (KIM'S KNEE HIGH PURPLE CONEFLOWER), GALLON POT					12		12			12		12	12		12					72
K0012975	PERENNIAL PLANTS, EUONYMUS FORTUNEI COLORATA (PURPLELEAF WINTER CREEPER), 4" POT			18	15		12		12	12		12			12		12	12			117
K0012990	PERENNIAL PLANTS, HEMEROCALLIS STRAWBERRY CANDY (STRAWBERRY CANDY DAYLILY), GALLON POT																		20	10	30
K0012990	PERENNIAL PLANTS, HEUCHERA SANGUINEA PALACE PURPLE (PALACE PURPLE CORALBELLS), GALLON POT				19																19
K0012993	PERENNIAL PLANTS, MISCANTHUS SINENSIS GRACILLIMUS (GRACILLIMUS MAIDEN GRASS), 3 GALLON POT		4		9																13
K0012993	PERENNIAL PLANTS, PANICUM VIRGATUM SHENENDOAH (BURGUNDY SWITCH GRASS), 3 GALLON POT																		4	4	8
K0012990	PERENNIAL PLANTS, RUDBECKIA FULGIDA GOLDSTRUM (GOLDSTURM BLACK -EYED SUSAN), GALLON POT		12																		12
K0012990	PERENNIAL PLANTS, SPOROBOLUS HETEROLEPIS (PRAIRIE DROPSEED), GALLON POT		8		16																24

* STATION/OFFSETS FOR PLANTER BOXES WITHOUT TREES ARE FOR REFERENCE PURPOSES ONLY AND SHALL NOT BE USED FOR PLANTER BOX CONSTRUCTION. SEE STREETSCAPE PLAN FOR STATION/OFFSET CONTROL POINT INFORMATION AT CORNERS OF NON STANDARD BOXES.
** STATION/OFFSETS FOR PLANTER BOXES WITH TREES REPRESENT THE CENTER OF TREE AND SHALL NOT BE USED FOR PLANTER BOX CONSTRUCTION. SEE STANDARD PLANTER BOX DETAIL FOR CONTROL POINT INFORMATION.

Farnsworth GROUP
7707 N. KNOXVILLE AVE. SUITE 100
PEORIA, ILLINOIS 61614
(309) 689-9888 / (309) 689-9820 Fax
www.f-w.com

FILE NAME = pw:\pwise_work\do_not_delete\dms73427\D49\L8155-sht-schedule-plant02.dgn	USER NAME = davsa08070	DESIGNED - BAB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TIGER II – WAREHOUSE DISTRICT SCHEDULE OF QUANTITIES – PLANTING	F.A.U RTE. 9213 9223	SECTION 12-00356-01-PV
		DRAWN - JTC	REVISED -			COUNTY PEORIA	TOTAL SHEETS 519
	PLOT SCALE = 2.0000 ' / in.	CHECKED - PJM	REVISED -			SHEET NO. 37	CONTRACT NO.89626
	PLOT DATE = 08\23\2012	DATE - 7/18/12	REVISED -		SCALE: N.T.S. / SHEET NO. OF SHEETS / STA. TO STA.	ILLINOIS	FED. AID PROJECT TIG-5093(158)