



NOTE 1:
 CROSSWALK PAVEMENT MARKINGS SHALL BE PLACED IN THE CENTER OF THE CONCRETE BANDING ON EITHER SIDE OF THE BRICK PAVER SIDEWALK ON RIGID BASE. PRIMER SHALL BE APPLIED AS INDICATED IN THE STANDARD SPECIFICATIONS.

- ① DOUBLE YELLOW THERMOPLASTIC PAVEMENT MARKING LINE - 4" SOLID, 4" GAP
- ② WHITE THERMOPLASTIC PAVEMENT MARKING LINE - 8" SOLID
- ③ WHITE THERMOPLASTIC PAVEMENT MARKING LINE - 12" (ON 45° ANGLE, 20' CTC)
- ④ WHITE THERMOPLASTIC PAVEMENT MARKING LINE - 8" (2' LONG, 6' GAP)
- ⑤ WHITE THERMOPLASTIC PAVEMENT MARKING LINE - 10' LONG, 30' GAP - 4"
- ⑥ WHITE PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - 10' LONG, 30' GAP - 4"
- ⑦ WHITE PREFORMED THERMOPLASTIC STOP BAR PAVEMENT MARKING LINE - 24" SOLID
- ⑧ WHITE PREFORMED THERMOPLASTIC PAVEMENT MARKING LINE - 8" SOLID
- ⑨ PREFORMED THERMOPLASTIC PAVEMENT MARKING, LETTERS (6' HEIGHT) AND SYMBOLS (FOR LEFT AND RIGHT TURN LANE ONE ARROW 20' FROM FRONT OF STORAGE AND ONE ARROW 20' AT BACK OF STORAGE)



FILE NAME =	USER NAME = daws00070	DESIGNED = MGD	REVISED =	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ADAMS STREET PAVEMENT MARKING PLANS				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
o:\pwise_work\do_not_delete\des73380\04	2_0155-shr-gmk895.dgn	DRAWN = RLA	REVISED =		12-00356-01-PV	PEORIA	519	90					
	PLOT SCALE = 3/8" = 1' / in.	CHECKED = KNB	REVISED =		SCALE: 1"=20'				SHEET NO. OF SHEETS STA. 162+50 TO STA. 166+00				
	PLOT DATE = 08/23/2012	DATE = 7/18/12	REVISED =		CONTRACT NO. 89626				ILLINOIS FED. AID PROJECT TIG-509315B				