


- ① WHITE PREFORMED THERMOPLASTIC STOP BAR PAVEMENT MARKING LINE - 24" SOLID
- ② WHITE THERMOPLASTIC PAVEMENT MARKING LINE - 8" SOLID
- ③ YELLOW THERMOPLASTIC PAVEMENT MARKING LINE - 12" (ON 45° ANGLE, 20' CTC)
- ④ WHITE THERMOPLASTIC PAVEMENT MARKING - LINE 12" (ON 45° ANGLE, 20' CTC)
- ⑤ PREFORMED THERMOPLASTIC PAVEMENT MARKING, LETTERS AND SYMBOLS (FOR LEFT AND RIGHT TURN LANE ONE ARROW 20' FROM FRONT OF STORAGE AND ONE ARROW 20' AT BACK OF STORAGE)
- ⑥ WHITE THERMOPLASTIC PAVEMENT MARKING LINE - 8" (2' LONG, 6' GAP)
- ⑦ DOUBLE YELLOW THERMOPLASTIC PAVEMENT MARKING LINE - 4" SOLID
- ⑧ WHITE PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4" - 10' LONG, 30' GAP
- ⑨ YELLOW PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4" - 10' LONG, 30' GAP
- ⑩ YELLOW THERMOPLASTIC PAVEMENT MARKING LINE - 4" SOLID

© Copyright CMT, Inc.



**CMT**  
**CRAWFORD, MURPHY & TILLY, INC.**  
 CONSULTING ENGINEERS  
 License No. 184-000613

FILE NAME *	USER NAME * monak01398	DESIGNED - RMM/EMM	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>OAK STREET PAVEMENT MARKING PLANS</b>	F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
o:\pwise_work\do_not_delete\dms73328\04	12-0155-shc-pw-markings-086.dgn	DRAWN - RJE	REVISED -			12-00356-01-PV	PEORIA	519	100	
PLOT SCALE * 3/4" = 1' / in.	CHECKED - EJM	REVISED -	REVISED -			CONTRACT NO. 89626		ILLINOIS FED. AID PROJECT YIG-6093458		
PLOT DATE * 07/23/2012	DATE - 7/18/12	REVISED -	REVISED -			SCALE: 1" = 20'	SHEET NO. OF SHEETS	STA. 793+65.00 TO STA. 796+00.00		