


REPAIR DESCRIPTIONS

REPAIR 3571 - REMOVE AND REPLACE WITH NEW THE EXISTING CASTING AND LID OF MANHOLE ESAN-4. CAREFULLY REMOVE ANY LOOSE BRICKS BELOW THE EXISTING CASTING AND LID AND REPLACE THEM WITH ADJUSTING RINGS IN ACCORDANCE WITH GPSD SPECIFICATIONS.

REPAIR 3572 - REMOVE AND REPLACE WITH NEW THE EXISTING CASTING AND LID OF MANHOLE ESAN-2. CAREFULLY REMOVE ANY LOOSE BRICKS BELOW THE EXISTING CASTING AND LID AND REPLACE THEM WITH ADJUSTING RINGS IN ACCORDANCE WITH GPSD SPECIFICATIONS.

REPAIR 3573 - REMOVE AND REPLACE WITH NEW THE EXISTING CASTING AND LID OF MANHOLE ESAN-3. CAREFULLY REMOVE ANY LOOSE BRICKS BELOW THE EXISTING CASTING AND LID AND REPLACE THEM WITH ADJUSTING RINGS IN ACCORDANCE WITH GPSD SPECIFICATIONS.

SANITARY SCHEDULE	
	X6026056
LOCATION	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID
	EACH
REPAIR 3571	1
REPAIR 3572	1
REPAIR 3573	1
TOTAL	3



FILE NAME =	USER NAME = kovan@1511	DESIGNED - PWM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ADAMS STREET AND JEFFERSON AVENUE SANITARY SEWER PLANS	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca\pwise_work\do_not_delete\dms73328\04	12.0155-ah-01.dgn	DRAWN - RLA	REVISED -			12-00356-01-PV	PEORIA	519	210	
	PLOT SCALE = 3/4" = 1' / in.	CHECKED - CAL	REVISED -			CONTRACT NO.89626				
	PLOT DATE = 07/23/2012	DATE - 7/18/12	REVISED -			ILLINOIS FED. AID PROJECT TIG-50931(58)				
				SCALE: 1"=20'		SHEET NO. OF SHEETS STA. TO STA.				

