



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

November 1, 2012

SUBJECT: Various Routes
Project TE-00D9(103)
Section 10-00061-00-SW (Benton)
Franklin County
Contract No. 99486
Item 051
November 9, 2012 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

1. Revised page 36 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger', followed by the letters 'P.E.' in a smaller font.

By: Ted B. Walschleger, P.E.
Engineer of Project Management

The Contractor shall provide the following warranties:

1. For a period of one year plus one additional growing season following the date of substantial completion, plant material installed under this contract shall be replaced if necessary according to these specifications.
2. If at any time during the warranty period a plant dies, becomes diseased or unsightly, the Architect/Engineer may request immediate or future scheduled replacement and the Contractor shall promptly comply.

Measurement and payment shall be made per Unit (UNIT). One unit is equal to one each plant.

Pay Item: Z0018100 - DRAINAGE STRUCTURE ADJUSTMENT (SPECIAL):

This Pay Item shall consist of all labor, equipment and material necessary to adjust existing drainage structures and storm water curb openings, combination inlets and drains, vaults, piping and other miscellaneous storm drainage structures at locations shown on the plans or designated by the Architect/Engineer. Work shall include all required demolition, reconstruction and resetting of existing and new bases, columns, covers, pipe alterations/extensions and all other required adjustments to existing and new materials to provide a finish elevation flush to adjacent new grades and existing and new pavement materials and to provide positive drainage to the drainage structure/inlet. All cost associated with this work shall be considered part of this Pay Item and no additional compensation will be allowed.

Measurement and payment shall be made per Each (EACH).

Pay Item: Z0018200 - DRAINAGE STRUCTURE RECONSTRUCTION (SPECIAL):

This Pay Item shall consist of all labor, equipment and material necessary for furnishing and installing new cast iron storm water curb openings, combination inlets, drainage structures and drains at locations shown on the plans or designated by the Architect/Engineer. Work shall include all required bases, columns, covers, pipe alterations/extensions and all required adjustments to existing materials to provide a finish elevation flush to adjacent existing and new grades and existing and new pavement materials and to provide positive drainage to the inlet. All cost associated with this work shall be considered part of this Pay Item and no additional compensation will be allowed.

The Contractor shall submit product data, samples, shop drawings and manufacturer's placement and instructions for:

1. Cut sheets for products proposed for use.
2. Shop drawings for product assembly and installation.

W&B Project No. 11-10-078

Benton - New Pedestrian Streetscape

Special Provisions-36

Revised 11-1-12